

DocLang: Universal AI Document Format

Version: 0.5

Contents

Introduction and Overview	6
Foreword	6
Introduction	6
Scope	7
Motivation	7
Language Design Principles	10
Terminology	10
Property Semantics	10
Content Encoding and Whitespace Handling	11
Head and Body Areas	11
Element Head	11
Element Body	11
Document Head	11
Document Body	12
Head and Body Example	12
Subclasses	12
Version Management and Compatibility	13
Semantic Versioning Principles	13
Version 0.x Behavior	13
XSD Schema Versioning	13
Language Specification	14
Usage Examples	15
Simple Document Structure	15
Pictures	15
Code snippets	16
Math and Equations	17
Lists	19
Tables	21
Fields	23
Field Structure Rules	24

Field region examples	24
Split structure	43
Cross-column structure example	43
Cross-page structure example	44
References	46
Cross-references	46
Hyperlinks	46
Formatting	47
Page Break with Continuation	47
Custom vocabularies	48
Bibliography	50
Appendix A: Reference	51
Special Elements	51
<doclang>	51
<head>	51
<page_break>	52
Semantic Elements	52
<text>	52
<heading>	53
<footnote>	53
<page_header>	53
<page_footer>	54
<field_region>	54
<list>	54
<table>	55
<index>	55
<formula>	56
<code>	56
<picture>	56
<marker>	57
<group>	57
<field_heading>	57
<field_item>	58

<key>	58
<value>	58
<hint>	59
<caption>	59
Property Elements.....	59
<label>	60
<thread>.....	60
<xref>	61
<href>	61
<custom>	61
<location>.....	62
<layer>	62
Payload Elements.....	63
<src>	63
<checkbox>	63
<content>.....	64
Formatting Elements.....	64
<bold>	64
<italic>	64
<underline>	65
<striketrough>.....	65
<superscript>.....	65
<subscript>	66
<handwriting>.....	66
<rtl>	66
Structural Elements	67
<fccl>	67
<eccl>	67
<ched>.....	67
<rhed>.....	67
<corn>	68
<srow>	68
<lcel>	68

<ucel>	68
<xcel>	69
<nl>	69
<ldiv>.....	69
Document Head Elements	70
<default_resolution>.....	70
Appendix B: Recommendations	71
Recommended labels	71
Pictures.....	71
Code	71
Custom vocabulary naming and namespacing.....	72
Token vocabulary	72
Appendix C: Future Extensions.....	76
Horizontal Threading.....	76
Metadata	76
<head>	76

Introduction and Overview

Foreword

This specification was prepared by

Name	Company
Peter Staar	IBM
Panos Vagenas	IBM
Maksym Lysak	IBM
Nikolaos Livathinos	IBM
Christoph Auer	IBM
Michele Dolfi	IBM
Said Gürbüz	IBM
Santosh Borse	IBM
Yousaf Shah	IBM
Maroun Touma	IBM
Christopher Giblin	IBM
Marlene Wolfgruber	ABBYY
Maxime Vermeir	ABBYY
Morgan Logue	ABBYY
Andrew Pery	ABBYY
Jehlum Vitasta Pandit	RedHat
Ali Maredia	RedHat
Micaela Kaplan	HumanSignal
Ryan Chesler	NVIDIA
Riccardo Maggioni	Forgis

This document specifies the DocLang format, a universal markup language for representing structured document content with semantic, geometric, and formatting information.

Introduction

The proliferation of digital documents across diverse formats (PDF, HTML, Word, etc.) has created significant challenges in document processing, conversion, and understanding. These were mainly designed for efficient rendering and often result in loss of semantic information, structural relationships, or geometric context during document conversion.

DocLang addresses these challenges by providing a minimalist, unambiguous markup format that:

- Preserves complete document structure and semantics
- Maintains geometric and layout information when appropriate
- Supports complex document components including tables, formulas, code, nested lists, and charts
- Enables lossless round-trip conversion between formats regarding content
- Maintains token efficiency by defining controlled vocabulary of tags and attributes

- Eliminates ambiguity by enforcing a well defined set of tags with restricted, non generic usage (and preserves semantic clarity)

This standard builds upon research in document understanding and is intended to represent the content of a document as accurately as possible while maintaining implementation simplicity.

Scope

This standard specifies:

- The syntax and semantics of the DocLang markup language
- Rules for encoding document structure, content, and metadata
- Primitives for representing geometric layout and pagination
- Methods for expressing formatting and text direction
- Specifications for complex document components (tables, charts, formulas, code, forms)
- Requirements for conforming implementations

Motivation


The motivation for this new markup language is twofold,

1. It is created from the ground up to be able to represent complex, multimodal content with visual grounding in plain text with markup
2. It is created with the express purpose to be compatible with LLM tokenizers, i.e. use a markup structure that maps naturally and efficiently between DocLang elements and LLM tokens.


As a consequence of point 2, this standard ensures that there is a limited number of tags and attributes. In general, we intend that the number of syntax tokens should not exceed 1000. The latter is not a strong bound, but rather a direction.

There is an exception for meta-data markup. Meta-data is not intended to be heavily used or produced by LLMs, so it is in general possible to include an expanded set of protected markup tokens. Nevertheless, we do want to normalize as much as possible this representation.

Such requirements preclude us from using existing markup languages such as Markdown (incomplete scope), HTML (not concise enough), LaTeX (ambiguity of representation) etc.



Example in pure table structure representation, omitting content of cells, when comparing HTML to DocLang (OTSL tags). HTML sequence is both longer and uses more tokens than DocLang



A specific class of related formats is the one operating on the OCR level, including PageXML, ALTO XML, and hOCR.

Beyond certain low-level similarities (e.g. presence of bounding box information), the DocLang format is significantly differentiated as it is designed to be AI-native:

- The above-mentioned formats focus on OCR processing, e.g. for archives, browser display, or other types of OCR/HTR pipelines, while DocLang is designed for LLM/VLM generation, with token efficiency in mind.
- Whereas these formats are primarily concerned with the geometric locations of the various spans of text, DocLang also places a strong focus on the semantic meaning and internal structure of the involved complex components, providing various native elements for headings, formulas, code, etc. and also rich table structure support (incl. table headings, spanned cells, etc.), this way capturing richer context for generative AI applications to leverage.

Language Design Principles

Terminology

Abstract concepts:

- **document component:** A cohesive and meaningful part of the document, e.g. a table, list item with a marker, a bold piece of text, etc.

Adopted from XML:

- **element:** An XML element.
- **attribute:** An XML attribute.
- **tag:** An XML tag: can be a start-tag, an end-tag, or an empty-element tag (a.k.a. self-closing tag).

Adopted from HTML:

- **block-level element:** An element that is meant to be interpreted or displayed as a block, i.e. starting on a new line, occupying the full width of its container, and typically with increased margin to any other neighboring block-level elements; a typical HTML example is the `p` element (paragraph).
- **inline element:** An element that can be used *within* a block element to shape its in-line structure; a typical HTML example is the `span` element.

Note that, whether block-level or inline, an element may contain *explicit* new lines.

Property Semantics

In XML, the attribute syntax allows explicitly separating an element's properties from its content. Let's consider the following example: `<elem size="250" color="#ffeedd">foo</elem>`. This denotes an `elem` element, including its properties (size and color) and its content (foo).

For an element with multiple possible property values, the attribute syntax can lead to an increased complexity of the respective possible tokenized representations. For instance, the following could all be valid variants of an `elem` start tag: `<elem size="300" color="#aabbcc">`, `<elem size="42">`, `<elem color="#112233">`, `<elem>`.

Aiming at LLM-friendliness, in such cases, the DocLang format often favors an alternative representation of property semantics, namely captured as respective elements leading the content. The example above could be represented as `<elem><size>250</size><color>#ffeedd</color>foo</elem>`. Depending on the specific properties, empty elements are used too.

This representation can reduce the number of tokens and streamline how XML is mapped to them, making it easier for language models to learn and predict.

For elements with a strictly limited set of possible property values, attributes are still used.

Content Encoding and Whitespace Handling

As DocLang is XML, standard XML encoding rules apply — for example:

- any provided XML prolog defines the encoding, otherwise UTF-8 is assumed
- special characters reserved by XML, such as `<`, can be represented either by escaping with the respective XML entities (e.g. `<` becomes `<`;) or by using CDATA section syntax (e.g. raw text `<foo>` can be represented as `<![CDATA[<foo>]]>`.)

DocLang generally allows applications to decide how to handle XML whitespace (i.e. implicit `xml:space="default"` behavior). To address cases where preservation is required, DocLang provides a dedicated element for whitespace preservation (i.e. `xml:space="preserve"` behavior).

Head and Body Areas

Documents and their core components (as implemented via semantic elements) can have various properties associated with them. To separate between properties and actual content, DocLang follows a two-part scheme, both on the the component / element level and on the global document level.

Element Head

The XML content of a semantic element begins with an *element head*, which is a sequence of dedicated elements that establish the element's properties, namely in this order:

- `<label>` (optional)
- `<thread>` (optional)
- `<xref>` or `<href>` (mutually exclusive, optional)
- `<layer>` (optional)
- optional sequence of 4 `<location>`s, whereby values are interpreted in alternating axis order, as `x_min`, `y_min`, `x_max`, `y_max` (after resolution normalization), w.r.t. the top-left corner of the page
- `<caption>` (optional)
- `<custom>` (optional)

Element Body

The XML content after the element head is called the *element body* and contains the effective payload of the semantic element.

Document Head

Root element `<doclang>` begins with an optional *document head*, which encapsulates any global document properties in a dedicated `<head>` element.

Document Body

The remaining XML content after the optional document head is called the *document body* and contains the effective payload of the document.

Head and Body Example

While the details are specified in the sections further below, this snippet shows an example of this scheme:

```
<doclang>
  <!-- document head: -->
  <head>
    <default_resolution width="1024" height="1024"/>
    <!-- ... -->
  </head>

  <!-- document body: -->
  <text>

    <!-- element head: -->
    <location value="60"/><location value="260"/>
    <location value="440"/><location value="270"/>

    <!-- element body: -->
    <italic>Hello</italic>
    <content> world!</content>

  </text>
  <text>
    <!-- element body: -->
    Headless paragraph
  </text>
</doclang>
```

Subclasses

For core document components like `<picture>` or `<code>`, a subclass may be indicated via the `<label>` element. DocLang provides some recommended value domains (see Appendix B: Recommendations), but for extensibility purposes, the label value is not to be validated. Additionally, some elements, e.g. `<picture>`, may include a `class` attribute for providing an intermediate classification level typically associated with specific semantics and structural implications.

In the example further below:

- `class="chart"` means the picture is semantically considered a chart and is therefore associated with special structuring rules (in the case of a chart, it can namely contain structured chart data in OTSL format)
- the label value is conveying the specific chart subclass for further classification purposes

```
<doclang>
  <picture class="chart">
    <label value="bar_chart"/>
    <table><!-- structured chart data in OTSL ... --></table>
  </picture>
</doclang>
```

Version Management and Compatibility

DocLang documents define a version in MAJOR.MINOR format through the `version` attribute of the root `<doclang>` element. This indicates the specification version against which the document is intended to be validated.

Semantic Versioning Principles

The XSD schema used for validating DocLang XML documents defines the specification versions it supports based on Semantic Versioning principles, i.e. considering $X \geq 1$, and $Y < Z$:

- A document with version $X.Y$ is compatible with an XSD schema with version $X.Z$, i.e. a document that is valid against schema $X.Y$ will also successfully validate against schema $X.Z$.
- A document with version $X.Z$ is considered incompatible with an XSD schema with version $X.Y$, i.e. a document that is valid against schema $X.Z$ need not be successfully validate against $X.Y$.

Example:

- A 1.0 document is compatible with a 1.1 schema
- A 1.1 document is considered incompatible with a 1.0 schema

Version 0.x Behavior

As per Semantic Versioning conventions, versions where MAJOR = 0 indicate initial development and always break backward compatibility. Therefore:

- A document of version 0.1 is considered incompatible with a 0.2 schema
- A document of version 0.2 is considered incompatible with a 0.1 schema

Each minor version increment in the 0.x series represents a breaking change.

XSD Schema Versioning

The XSD schema itself may additionally capture a patch version and internally define a full Semantic Versioning (SemVer) version string (e.g., $1.0.0$, $1.0.1$) to track schema-level changes that do not affect document compatibility.

Language Specification

The individual DocLang elements and attributes, as well as DocLang's contextual rules are specified in Appendix A: Reference.

Non-normative recommendation guidelines are covered in Appendix B: Recommendations.

Planned extensions are discussed in Appendix C: Future Extensions.

Machine-checkable conformance is defined by the DocLang reference validator.

Usage Examples

Simple Document Structure

In the simplest document example, document elements are in a flat list,

```
<doclang>
  <heading>Research Paper Title</heading>
  <heading level="2">Abstract</heading>
  <text>This paper presents...</text>
  <heading level="2">Introduction</heading>
  <text>In recent years...</text>
  <heading level="3">Background</heading>
  <text>Previous work has shown...</text>
</doclang>
```

In case of page-layout information, the coordinates are provided only at the semantic element level. Coordinates are not allowed at the group level.

```
<doclang>
  <heading>
    <location value="10"/><location value="20"/><location value="30"/><location
value="40"/>
    Research Paper Title
  </heading>

  <heading level="2">
    <location value="10"/><location value="20"/><location value="30"/><location
value="40"/>
    Abstract
  </heading>
  <text>
    <location value="10"/><location value="20"/><location value="30"/><location
value="40"/>
    This paper presents...
  </text>

  <heading level="2">Introduction</heading>
  <text>In recent years...</text>

  <heading level="3">Background</heading>
  <text>Previous work has shown...</text>
</doclang>
```

Pictures

Pictures are captured with the `<picture>` element and may be specialized via the `class` attribute, as detailed in the reference. The picture data can be provided via the `<src>` element as a URI capturing the image either by reference (e.g. https URL) or as base64-encoded data (RFC 2397).

Picture by reference URI:

```
<picture>
  <src uri="https://example.com/image.jpg"/>
</picture>
```

Picture by base64-encoded data:

```
<picture>
  <src
uri="data:image/png;base64,iVBORw0KGgoAAAANSUhEUgAAAAEAAAABACAIAAAAI1C+aJAAAAIk1EQVR4nO3BAQ0AAADCoPDPbQ8HFAAAAAAAAAAAAAAAAAA8G4wQAABiwCo9wAAAAABJRUS5ErkJggg==" />
</picture>
```

Bar chart using recommended label and `<table>` for capturing chart data in OTSL format:

```
<picture class="chart">
  <label value="bar_chart"/>
  <table>
    <ched/>Category<ched/>Value<nl/>
    <fcel/>A<fcel/>10<nl/>
    <fcel/>B<fcel/>20<nl/>
  </table>
  <src uri="chart.svg"/>
</picture>
```

Code snippets

Code content is captured with `<code>`, either as a standalone block or inlined within a semantic element. For language classification, use a `<label>` in the element head (see Appendix B: Recommendations).

Whitespace can be retained by `<content>` and XML escape characters can be addressed using CDATA.

Inline code:

```
<text>
  Check your version with <code>python --version</code>.
  We can even have <code><b>formatted code</b></code>.
</text>
```

Code block with language classification and whitespace preservation:

```
<code>
  <label value="Python"/>
  <content>
def add(a, b):
    return a + b

    if __name__ == "__main__":
        print(add(2, 3))</content>
</code>
```

Grouped code with caption and coordinates:

```

<group>
  <caption>
    <location value="10"/><location value="20"/><location value="400"/><location
value="60"/>
    Listing 1: Minimal HTTP server
  </caption>
  <code>
    <label value="JavaScript"/>
    <location value="10"/><location value="80"/><location value="400"/><location
value="300"/>
    <content><![CDATA[
// Minimal Node.js server
import http from 'node:http';
const server = http.createServer((req, res) => {
  res.end('OK');
});
server.listen(3000);]]></content>
  </code>
  <footnote>Source: examples/code/server.js</footnote>
</group>

```

Long code blocks can be split across pages using continuation elements; keep `<label>` in the first fragment.

```

<code>
  <label value="Shell"/>
  <thread thread_id="42"/>
  <content>
    # Part 1
    seq 1 5 | while read n; do echo $n; done</content>
</code>
<page_footer>Foo</page_footer>
<page_break/>
<code>
  <thread thread_id="42"/>
  <content>
    echo "done"</content>
</code>

```

Math and Equations

All math is authored as LaTeX inside `<formula>`, whether in standalone blocks or inlined within a semantic element (similar to code).

Inline formula:

```

<text>
  The famous relation <formula> $E = mc^2$ </formula> connects mass and energy.
  For small  $x$ , <formula> $\sin x \approx x - x^3/3!$ </formula> holds.
  The binomial: <formula> $(a+b)^n = \sum_{k=0}^n \binom{n}{k} a^{n-k} b^k$ </formula>.
</text>

```

Block Formula:

```
<formula>
  \int_{-\infty}^{\infty} e^{-x^2}\,dx = \sqrt{\pi}
</formula>
```

Grouped formula with caption and coordinates:

```
<group>
  <caption>
    <location value="10"/><location value="20"/><location value="400"/><location
value="60"/>
    Equation for the normal distribution
  </caption>
  <marker>(2)</marker>
  <formula>
    <location value="10"/><location value="80"/><location value="400"/><location
value="150"/>
    f(x) = \frac{1}{\sigma\sqrt{2\pi}}\,\exp\!\left(-\frac{(x-\mu)^2}{2\sigma^2}\right)
  </formula>
  <footnote>Parameters: mean <formula>\mu</formula> and standard deviation
<formula>\sigma</formula>.</footnote>
</group>
```

Multi-line LaTeX in a single formula:

```
<formula>
  <content><![CDATA[
    \begin{align}
      \nabla\!\cdot\!\mathbf{E} &= \frac{\rho}{\varepsilon_0} \\\
      \nabla\!\cdot\!\mathbf{B} &= 0
    \end{align}]]></content>
</formula>
```

Cross-page block formula with continuation:

```
<formula>
  <content>
    \begin{equation}
      \mathbf{F}(t) = \int_0^t e^{A(t-\tau)}\,\mathbf{b}(\tau)\,d\tau
    \end{equation}</content>
    <thread thread_id="42"/>
</formula>
<page_footer>Foo</page_footer>
<page_break/>
<formula>
  <thread thread_id="42"/>
  <content>
    % Optional tail content if the printed equation spans pages</content>
</formula>
```

Note: All math content is LaTeX; omit $\dots$ or $\left[\dots\right]$ delimiters since the tag conveys math context.

Lists

A list can contain as list items any semantic element sequence. List items are namely introduced by `<ldiv>` elements, whereby an `<ldiv>` may optionally contain a marker. This means that a non-empty `<list>` element body must begin with an `<ldiv>`.

To promote token efficiency within the repetitive context of a list, a list item may also comprise unwrapped text content. That case is called a *virtual `<text>`* and is to be handled exactly as if the whole list item (content between two sibling `<ldiv>`s or until `</list>`) were wrapped by `<text>` tags.

Basic list with virtual `<text>`

```
<list>
  <ldiv/>First item
  <ldiv/>Second item
  <ldiv/>Third item
</list>
```

Unordered list with optional markers

```
<list class="unordered">
  <ldiv><marker>•</marker></ldiv>
  <text>First item with <bold>bold</bold> text</text>
  <ldiv>
    <!-- Marker with its own coordinates -->
    <marker>
      <location value="50"/><location value="110"/><location value="60"/><location
value="120"/>
      •
    </marker>
  </ldiv>
  <text>Second item</text>
</list>
```

Ordered list; markers are optional and can hold the printed numbering

```
<list class="ordered">
  <ldiv><marker>1.</marker></ldiv>
  <text>Install dependencies</text>
  <ldiv><marker>2.</marker></ldiv>
  <text>Run tests</text>
  <ldiv/>
  <!-- No marker provided -->
  <text>Ship release</text>
</list>
```

Checkbox items with selection state; markers optional

```
<list class="unordered">
  <ldiv><marker><checkbox class="selected"/></marker></ldiv>
  <text>Completed task</text>
  <ldiv><marker><checkbox class="unselected"/></marker></ldiv>
```

```
<text>Pending task</text>
</list>
```

Nested lists (mixing ordered and unordered)

```
<list class="ordered">
  <ldiv><marker>1.</marker></ldiv>
  <text>Setup project</text>
  <list class="unordered">
    <ldiv><marker>•</marker></ldiv>
    <text>Create virtual environment</text>
    <ldiv><marker>•</marker></ldiv>
    <text>Configure linter</text>
  </list>
  <ldiv><marker>2.</marker></ldiv>
  <text>Implement features</text>
</list>
```

Page breaks and continuation

Lists can span multiple pages. Use `<thread thread_id="...">` to indicate continuation. You may thread the whole list and, if a particular component, e.g. a `<text>` is broken, also thread the component itself.

List split across pages

```
<list class="ordered">
  <thread thread_id="L1"/>
  <ldiv><marker>1.</marker></ldiv>
  <text>First item</text>
  <ldiv><marker>2.</marker></ldiv>
  <text>Second item</text>
</list>
<page_break/>
<list class="ordered">
  <thread thread_id="L1"/>
  <ldiv><marker>3.</marker></ldiv>
  <text>Third item</text>
</list>
```

Single list-item broken by a page break

```
<list class="unordered">
  <thread thread_id="L2"/>
  <ldiv><marker>•</marker></ldiv>
  <text>
    <thread thread_id="I7"/>
    This item starts on page 1 and continues
  </text>
</list>
<page_break/>
<list class="unordered">
  <thread thread_id="L2"/>
```

```

</div>
<text>
  <thread thread_id="I7"/>
  on page 2 until it ends.
</text>
</list>

```

Notes

- `<marker>` is optional. Include it when the printed glyph/number is visible.
- `<marker>` may begin with an element head (e.g. `<location>` coordinates to pinpoint bullet/number placement) before the visible glyph or `<checkbox>`.
- Lists can nest as shown above.
- When broken across pages, close items before the `page_break`, then re-open and continue with matching `thread` ids after the break.

Tables

A table is defined by a `<table>` element, that contains cells, as delimited by the respective OTSL structural elements (e.g., `<fcel/>`, `<ched/>`). This means that a non-empty `<table>` element body must begin with such an OTSL structural element.

Similarly to lists above, while a cell can naturally contain any semantic element sequence, it may also comprise unwrapped text content too, i.e. constituting a virtual `<text>`.

Basic table with virtual `<text>`:

```

<table>
  <ched/>Method<ched/>Accuracy<nl/>
  <fcel/>Baseline<fcel/>0.8<nl/>
  <fcel/>Proposed<fcel/>0.92<nl/>
</table>

```

Example with table location and semantic elements:

```

<table>
  <location value="40"/><location value="130"/><location value="540"/><location
value="320"/>
  <ched/><text>Method</text><ched/><text>Accuracy</text><nl/>
  <fcel/><text>Baseline</text><fcel/><text>0.85</text><nl/>
  <fcel/><text>Proposed</text><fcel/><text>0.92</text><nl/>
</table>

```

Example with caption and footnote:

A `group` element can be employed for associating a table with other semantic elements, such as a caption or a footnote — for instance:

```

<group>
  <caption>
    <location value="40"/><location value="80"/><location value="540"/><location

```

```

value="110"/>
  Table 1: Experimental Results
</caption>
<table>
  <location value="40"/><location value="130"/><location value="540"/><location
value="320"/>
  <ched/><text>Method</text><ched/><text>Accuracy</text><nl/>
  <fcel/><text>Baseline</text><fcel/><text>0.85</text><nl/>
  <fcel/><text>Proposed</text><fcel/><text>0.92</text><nl/>
</table>
<footnote>Accuracy reported on validation set.</footnote>
</group>

```

Immediately after a cell-creating element (e.g., `<fcel/>`, `<ched/>`), place the cell's content, which may include `text`, `list`, even nested `group` elements like another `table` or `picture`.

```

<group>
  <caption>Table 3: Rich Cells</caption>
  <table>
    <location value="40"/><location value="200"/><location value="560"/><location
value="620"/>
    <ched/><text>Description</text><ched/><text>Details</text><nl/>
    <fcel/>
    <text>Pipeline steps</text>
    <fcel/>
    <list class="unordered">
      <ldiv><marker>•</marker></ldiv>
      <text>Ingest</text>
      <ldiv><marker>•</marker></ldiv>
      <text>Process</text>
      <ldiv><marker>•</marker></ldiv>
      <text>Export</text>
    </list>
    <nl/>
    <fcel/>
    <text>Nested table</text>
    <fcel/>
    <group>
      <caption>Inner table</caption>
      <table>
        <ched/>
        <text>Key</text>
        <ched/>
        <text>Value</text>
        <nl/>
        <fcel/>
        <text>A</text>
        <fcel/>
        <text>1</text>
        <nl/>
        <fcel/>
        <text>B</text>

```

```

        <fcel/>
        <text>2</text>
        <nl/>
    </table>
</group>
<nl/>
<fcel/>
<text>Image</text>
<fcel/>
<picture>
    <caption>Example image inside a cell</caption>
    <src uri="assets/img/sample.png"/>
</picture>
<nl/>
</table>
</group>

```

Notes:

- OTSL follows the rectangular rule; ensure each row has the same number of structural elements up to `<nl/>`.
- A cell can include any valid DocLang semantic element sequence.

Fields

Fields provide a flexible structure for representing key-value data and structured content. The field elements allow for more flexible document structures where keys and values may be separated by other content or organized in complex layouts.

element	Description
<code><field_region></code>	Field region container; can contain <code>field_item</code> elements as descendants
<code><field_item></code>	Field item container; may contain 0-1 key and 0-many <code>value</code> elements as descendants
<code><field_heading></code>	Field heading within a field region; has an optional attribute <code>level</code>
<code><key></code>	Key of the field item: can be a descendant of <code>field_item</code>
<code><value></code>	Value of the field item: can be a descendant of <code>field_item</code> ; optional <code>class</code> attribute with values <code>read_only</code> (default) or <code>fillable</code>
<code><hint></code>	Hint for a fillable value field; recommended to be used within the context of a <code>field_item</code> ; can describe a format, example, or additional description

Note that all of the above are semantic elements and can therefore contain their own element head, including e.g. their own bounding box location information.

Field Structure Rules

- Any `field_heading` or `field_item` must be a descendant of a `field_region` (not necessarily a direct child)
- Any `key` or `value` element must be a descendant of a `field_item` (not necessarily a direct child)

— More precisely, 0 or 1 `key` element and 0 or more `value` elements are allowed within a single `field_item`

- For a given `field_item`, the 0..1 `key` constraint applies to its own descendant scope, excluding descendants that belong to nested `field_item` elements
- This way, the `field_item` can serve for associating the `values` with a `key`
- The `value` element has an optional `class` attribute:
 - `class="read_only"` (default): Indicates a pre-filled, non-editable value
 - `class="fillable"`: Indicates an empty or editable field that can be filled in
- The `hint` element is recommended to be used within a `field_item` context to provide guidance for relevant field elements, such as fillable values.
- All field elements are semantic elements and can therefore contain their own element head, including e.g. their own bounding box location information.

Field region examples

Basic field region with simple key-value pairs:

```
<field_region>
  <field_item>
    <key>Name:</key>
    <value>John Smith</value>
  </field_item>
  <field_item>
    <key>Date of Birth:</key>
    <value>1985-03-15</value>
  </field_item>
  <field_item>
    <key>Address:</key>
    <value>123 Main Street, Anytown, USA</value>
  </field_item>
</field_region>
```

Field region with headings and complex layout:

```
<field_region>
  <field_heading>Personal Information</field_heading>

  <field_item>
    <text><key>Full Name:</key></text>
    <text><value>Jane Doe</value></text>
  </field_item>

  <field_item>
```

```

    <text><key>Email:</key></text>
    <text><value>jane.doe@example.com</value></text>
</field_item>

<field_heading level="2">Employment Details</field_heading>

<field_item>
  <text><key>Company:</key></text>
  <text><value>Acme Corporation</value></text>
</field_item>

<field_item>
  <text><key>Position:</key></text>
  <text><value>Senior Engineer</value></text>
</field_item>
</field_region>

```

Field item with multiple values:

```

<field_region>
  <field_item>
    <key>Phone Numbers:</key>
    <value>+1-555-0100 (Home)</value>
    <value>+1-555-0101 (Work)</value>
    <value>+1-555-0102 (Mobile)</value>
  </field_item>
</field_region>

```

Field item without a key (value-only):

```

<field_region>
  <field_heading>Additional Notes</field_heading>
  <field_item>
    <value>This is a standalone value without an explicit key.</value>
    <value>Multiple values can be provided.</value>
  </field_item>
</field_region>

```

Fillable fields with hints:

```

<field_region>
  <field_heading>Application Form</field_heading>

  <field_item>
    <key>Full Name:</key>
    <value class="fillable"></value>
    <hint>Enter your first and last name</hint>
  </field_item>

  <field_item>
    <key>Date of Birth:</key>
    <value class="fillable"></value>
    <hint>Format: YYYY-MM-DD</hint>
  </field_item>

```

```

</field_item>

<field_item>
  <key>Email Address:</key>
  <value class="fillable"></value>
  <hint>example@domain.com</hint>
</field_item>

<field_item>
  <key>Status:</key>
  <value class="read_only">Pending Review</value>
</field_item>
</field_region>

```

Field region with mixed content:

```

<field_region>
  <location value="50"/><location value="100"/>
  <location value="500"/><location value="400"/>

  <field_heading>Product Specifications</field_heading>

  <text>The following specifications apply to Model XYZ-2000:</text>

  <field_item>
    <key>Dimensions:</key>
    <value>10cm x 15cm x 5cm</value>
  </field_item>

  <field_item>
    <key>Weight:</key>
    <value>250g</value>
  </field_item>

  <picture>
    <src uri="assets/product-diagram.png"/>
    <caption>Product diagram showing key components</caption>
  </picture>

  <field_item>
    <key>Materials:</key>
    <list class="unordered">
      <ldiv><marker>•</marker></ldiv>
      <text><value>Aluminum alloy frame</value></text>
      <ldiv><marker>•</marker></ldiv>
      <text><value>Tempered glass display</value></text>
      <ldiv><marker>•</marker></ldiv>
      <text><value>Silicone rubber grips</value></text>
    </list>
  </field_item>
</field_region>

```

Simple key-values

Firma: Holcim Kies und Splitt GmbH	Datum: 23.08.2019	Blatt- Nr.: 1 / 2
Werk: Schalkholz	Werks- Nr.: 303.61 K	Petrograph. Typ: Quartiärer Sand + Kies

```
<field_region>
  <field_item>
    <key>Firma:</key>
    <value>Holcim ... GmbH</value>
  </field_item>
  <field_item>
    <key>Datum:</key>
    <value>23.08.2019</value>
  </field_item>
  ...
  <field_item>
    <key>Petrograph. Typ:</key>
    <value>Quartiarer Sand + Kies</value>
  </field_item>
</field_region>
```

Nesting forms and using form headings

14. Transport information

Land transport ADR/RID and GGVS/GGVE (Germany)

GGVS/GGVE class: 8 Number and letter: 1B

ADR/RID class: 8 Number and letter: 1B

Name of material: 2796 SCHWEFELSAEURE

River transport ADN/ADNR

not examined

Sea transport IMDG

IMDG class: 9 UN-No.: 3316 Packaging group: II

Ems: 8-06 MFAG: 700

Correct technical name: CHEMICAL KIT

Air transport ICAO-TI and IATA-DGR

ICAO/IATA class: 9 UN/ID-No.: 3316 Packaging group: II

Correct technical name: CHEMICAL KIT

The transport regulations are cited according to international regulations and in the form applicable in Germany (GGVS/GGVE). Possible national deviations in other countries are not considered.

THESE TRANSPORT DATA APPLY TO THE ENTIRE PACK !

```
<field_region>
  <field_heading>
    <marker>14.</marker>
    Transport Information
  </field_heading>
  <field_region>
    <field_heading>
      Land transport ... (Germany)
    </field_heading>
    <field_item>
```

```

        <key>GGVS/GGVE class:</key>
        <value>8</value>
    </field_item>
    <field_item>
        <key>ADR/RID class:</key>
        <value>8</value>
    </field_item>
    ...
</field_region>
<field_item>
    <key>River transport ADN/ADNR</key>
    <value>not examined</value>
</field_item>
<field_region>
    <field_heading>
        Sea transport IMDG
    </field_heading>
    ...
</field_region>
...
<text>
    The transport ... considered.
</text>
<text>
    THESE TRANSPORT ... PACK!
</text>
</field_region>

```

Fillable form

<table><tr><td>

```

<field_region>
    <field_item>
        <key>Description</key>
        <value>A.A. Cat</value>
    </field_item>
    <field_item>
        <key>Quant.</key>
        <value></value>
    </field_item>
    <field_item>
        <key>Un</key>
        <value></value>
    </field_item>
    <field_item>
        <key>Measure</key>
        <value></value>
    </field_item>
    <field_item>
        <key>Price (in currency)</key>
        <value></value>
    </field_item>
    <field_item>

```

```

        <key>Un</key>
        <value></value>
    </field_item>
    <field_item>
        <key>Total</key>
        <value></value>
    </field_item>
    <text></text>
    <field_region>
        <field_item>
            <key>Delivery Cost</key>
            <value></value>
        </field_item>
        <field_item>
            <key>Maintenance</key>
            <value></value>
        </field_item>
        ...
    </field_region>
    <field_region>
        <field_item>
            <key>Date and time of delivery:</key>
            <value></value>
        </field_item>
        ...
        <field_item>
            <key>Guarantee</key>
            <value></value>
        </field_item>
        <text>
            Delivery Suppl...Finance Department
        </text>
    </field_region>
    ...
</field_region>

```

</td><td style="vertical-align: top;">

Description	A.A.Cat.	Quant.	Un Measure	Price (in currency)	
				Un	Total
Delivery Costs: Maintenance:			VAT: TOTAL:		
Date and time of delivery: Dispatched by: Final date of delivery or implementation: Payment Conditions: 60 Days from reception of correct invoice Guarantee:			Delivery Supplies must be delivered together with a copy of the present purchase order. Invoices must be issued to the OHIM and send <u>separately</u> to the attention of the Finance Department.		
Date of Issue and Signature of Authorising officer:	Date, Signature and Stamp for Supplier:		Date, Signature and Stamp for Acceptance:		

</td></tr></table>

Use of form headings

Alien's Change of Address Card		USCIS
Department of Homeland Security		Form AR-11
U.S. Citizenship and Immigration Services		OMB No. 1615-0007 Expires 08/31/2024
NOTE: An asterisk (*) indicates a mandatory field that must be completed.		
Information About You		
*Family Name (Last Name) staar	*Given Name (First Name) Peter	Middle Name (if applicable) WJ
I am in the United States as a: ☐ Visitor ☐ Student ☐ Permanent Resident ☐ Other (Specify)		
Country of Citizenship 		*Date of Birth (mm/dd/yyyy)
Alien Registration Number (A-Number) (if any) ▶ A-		
Information About Your Address		
*Present Physical Address (No PO Boxes)		
*Street Number and Name 	Apt. Ste. Flr. Number 	
*City or Town 	*State 	*ZIP Code
(USPS ZIP Code Lookup)		
Previous Physical Address		
Street Number and Name 	Apt. Ste. Flr. Number 	
City or Town 	State 	ZIP Code

```
<field_region>
  <field_heading>Information about you</field_heading>
  <field_item>
    <key>
      \*Family Name (Last Name)
    </key>
    <value>staar</value>
  </field_item>
  <field_item>
    <key>\*Given Name (First Name)</key>
    <value>peter</value>
  </field_item>
  <field_item>
    <key>\*Middle Name (if applicable)</key>
    <value>WJ</value>
  </field_item>
  <field_item>
    <key>I am in the United States as a:</key>
    <text><checkbox class="unselected"/>Visitor</text>
    <text><checkbox class="unselected"/>Student</text>
```

```

    <text><checkbox class="unselected"/>Permanent Resident</text>
    <text><checkbox class="unselected"/>Other (Specify)</text>
    <value></value>
  </field_item>
  <field_item>
    <key>Country of Citizenship</key>
    <value></value>
  </field_item>
  <field_item>
    <key>\*Date of Birth</key>
    <value></value>
  </field_item>
  <field_item>
    <key>Alien Registration Number (A-Number) (if any)</key>
    <value>A-</value>
  </field_item>
  <field_heading>Information About Your Address</field_heading>
  <text>\*Present Physical Address ()No Po Boxes</text>
  <field_item>
    <key>\*Street ... Name</key>
    <value></value>
  </field_item>
  <field_item>
    <key>Apt.</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_item>
    <key>Ste.</key>
    <checkbox class="unselected"/>
  </field_item>
  ...
</field_region>

```

High density form

SEZIONE II A - REDDITI SOGGETTI A IMPOSTA SOSTITUTIVA															
M31	REDDITI DI CAPITALE SOGGETTI AD IMPOSIZIONE SOSTITUTIVA	1	Tipo	2	Codice Stato estero	3	Ammontare reddito	4	Aliquota %	5	Credito IVCA	6	Proventi particolari	7	Opzione tassazione ordinaria
							.00				.00				
M32	PROVENTI DELLE OBBLIGAZIONI NON ASSOGGETTATI A IMPOSTA SOSTITUTIVA	1	Ammontare reddito	2	Aliquota %										
							.00								
M33	PROVENTI DERIVANTI DA DEPOSITI IN GARANZIA	1	Ammontare reddito				.00								
M34	BONUS E STOCK OPTION	1	Importo totale Bonus	2	Imponibile	3	Importo trattenuto dal sostituto								
			.00				.00			.00					
M35	PROVENTI DA ATTIVITÀ DI NOLEGGIO OCCASIONALE DI IMBARCAZIONI E NAVI DA DIPORTO	1	Importo totale proventi	2	Spese										
			.00				.00								
M36	REDDITI DA BENI SEQUESTRATI	1	Imponibile												
			.00												
M37	COMPENSI LEZIONI PRIVATE	1	Importo totale compensi	2	Eccedenza dichiarazione	3	Eccedenza compensata mod. F24	4	Acconti versati	5	Acconti sospesi	6	Opzione tassazione ordinaria		
			.00				.00		.00		.00		.00		
M38	FRONTALIERI SU RETRIBUZIONI SVIZZERE	1	Redditi da lavoro dipendente Svizzera	2	Imposta assolta in Svizzera	3	Contributo detraibile								
			.00				.00		.00						

```

<field_region>
  <field_heading>M31</field_heading>
  <field_heading level="2">REDDITI DI CAPITALE SOGGETTI AD IMPOSIZIONE
SOSTITUTIVA</field_heading>

```

```

<field_item>
  <marker>1</marker>
  <key>Tipo</key>
  <value></value>
</field_item>
<field_item>
  <marker>2</marker>
  <key>Codice Stato estero</key>
  <value></value>
</field_item>
<field_item>
  <marker>3</marker>
  <key>Ammontare reddito</key>
  <value>,00</value>
</field_item>
<field_item>
  <marker>4</marker>
  <key>Aliquota %</key>
  <value></value>
</field_item>
<field_item>
  <marker>5</marker>
  <key>Credito IVCA</key>
  <value>,00</value>
</field_item>
<field_item>
  <marker>6</marker>
  <key>Proventi particolari</key>
  <value></value>
</field_item>
<field_item>
  <marker>7</marker>
  <key>Opzione tassazione ordinaria</key>
  <value></value>
</field_item>
<field_heading>M32</field_heading>
<field_heading level="2">PROVENTI DELLE OBBLIGAZIONI NON ASSOGGETTATI A IMPOSTA
SOSTITUTIVA</field_heading>
<field_item>
  <marker>1</marker>
  <key>Ammontare reddito</key>
  <value>,00</value>
</field_item>
<field_item>
  <marker>2</marker>
  <key>Aliquota %</key>
  <value></value>
</field_item>
<field_heading>M33</field_heading>
<field_heading level="2">PROVENTI DERIVANTI DA DEPOSITI IN
GARANZIA</field_heading>
<field_item>
  <marker>1</marker>

```

```

    <key>Ammontare reddito</key>
    <value>,00</value>
  </field_item>
  ...
</field_region>

```

Classical duality between tables and explicit key-values

10.0	Adjusted CVSS v3.1 Score			
	Vector	AV:N/AC:L/PR:N/UI:N/S:U/C:N/I:L/A:H		
	Likelihood	Very High	Impact	Catastrophic
Affected Systems				
IP Address	Port	Service	Version	
10.0.0.101	80/tcp, 8088/tcp	Werkzeug	3.0.1	
10.0.0.102	80/tcp, 8088/tcp	Werkzeug	3.0.1	
10.0.0.103	80/tcp, 8088/tcp	Werkzeug	3.0.1	

```

<field_region>
  <field_item>
    <key>Adjusted CVSS v3.1 Score</key>
    <value>10.0</value>
  </field_item>
  <field_item>
    <key>Vector</key>
    <value>AV:N/AC:L/PR:N/UI:N/S:U/C:N/I:L/A:H</value>
  </field_item>
  <field_item>
    <key>Likelihood</key>
    <value>Very High</value>
  </field_item>
  <field_item>
    <key>Impact</key>
    <value>Catastrophic</value>
  </field_item>
  <field_heading>
    Affected Systems
  </field_heading>
  <table>
    <thead>
      <tr>
        <th>IP
Address</th>
        <th>Port</th>
        <th>Service</th>
        <th>Version</th>
      </tr>
    </thead>
    <tbody>
      <tr>
        <td>10.0.0.101</td>
        <td>80/tcp,
8088/tcp</td>
        <td>Werkzeug</td>
        <td>3.0.1</td>
      </tr>
      <tr>
        <td>10.0.0.102</td>
        <td>80/tcp,
8088/tcp</td>
        <td>Werkzeug</td>
        <td>3.0.1</td>
      </tr>
      <tr>
        <td>10.0.0.103</td>
        <td>80/tcp,
8088/tcp</td>
        <td>Werkzeug</td>
        <td>3.0.1</td>
      </tr>
    </tbody>
  </table>

```

</table>
</field_region>

Values without Keys

QUADRO W - Investimenti e attività estere di natura finanziaria o patrimoniale

SEZIONE I - DATI RELATIVI AGLI INVESTIMENTI E ALLE ATTIVITA'

	CODICE TITOLO POSSESSO	TIPO CONTRIBUENTE - IVAFE	CODICE INDIVIDUAZIONE BENE	CODICE STATO ESTERO	QUOTA DI POSSESSO	CRITERIO DETERMIN. VALORE	VALORE INIZIALE	VALORE FINALE		
	1	2	3	4	5	6	7	8		
							,00	,00		
W1	VALORE MASSIMO C/O PAESI NON COLLABORATIVI - IVAFE		GIORNI IVAFE - CRIPTO-ATTIVITA'		MESI IVIE	CREDITO D'IMPOSTA	DETRAZIONI - IVIE	QUOTA PARTECIPAZIONE - IVAFE	SOLO MONITORAGGIO	
	9		10		11	12	13	14	15	16
	,00					,00	,00			
	CODICE FISCALE SOCIETA' O ALTRA ENTITA' GIURIDICA IN CASO DI TITOLARE EFFETTIVO - IVAFE				CODICE FISCALE ALTRI COINTESTATARI				PRESENZA PIU' COINTESTATARI	REGIME FISCALITA' PRIVILEGIATA
	17	18			19			20	21	
W2	1	2	3	4	5	6	7	8		
							,00	,00		
	9	10	11	12	13	14	15	16		
	,00			,00	,00					
	17	18			19			20	21	

```
<heading>QUADRO W - Investimenti e...</heading>
<heading level="2">SEZIONE I - DATI RELATIVI...</heading>
<field_region>
  <field_heading>W1</field_heading>
  <field_item>
    <marker>1</marker>
    <key>CODICE TITOLO POSSESSO</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <key>TIPO CONTRIBUENTE - IVAFE</key>
    <value></value>
  </field_item>
  ...
  <field_heading>W2</field_heading>
  <field_item>
    <marker>1</marker>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <value></value>
  </field_item>
  <field_item>
    <marker>3</marker>
    <value></value>
  </field_item>
  ...
</field_region>
```

Another complex form deconstructed into field items

QUADRO C - Redditi di lavoro dipendente e assimilati														
SEZIONE I - REDDITI DI LAVORO DIPENDENTE E ASSIMILATI														
										Casi particolari		Codice Stato estero		
C1	1	2	3	4	C2	1	2	3	4	C3	1	2	3	4
	TIPO	INDETERMINATO/DETERMINATO	REDDITO (punti 1, 2, 3 CU 2025)	ALTRI DATI		TIPO	INDETERMINATO/DETERMINATO	REDDITO (punti 1, 2, 3 CU 2025)	ALTRI DATI		TIPO	INDETERMINATO/DETERMINATO	REDDITO (punti 1, 2, 3 CU 2025)	ALTRI DATI
			,00					,00					,00	
SOMME PER PREMI DI RISULTATO E WELFARE AZIENDALE														
C4	1	2	3	4	5	6	7	8	9					
	TIPOLOGIA LIMITE	SOMME A TASSAZIONE ORDINARIA	SOMME A IMPOSTA SOSTITUTIVA	RITENUTE IMPOSTA SOSTITUTIVA	BENEFIT	BENEFIT A TASSAZIONE ORDINARIA	TASSAZIONE ORDINARIA	TASSAZIONE SOSTITUTIVA	ASSENZA REQUISITI					
		,00	,00	,00	,00	,00								

<table><tr><td>

```

<heading>QUADRO C - Redditi di lavoro...</heading>
<field_region>
  <field_heading>SEZIONE I - RE...</field_heading>
  <field_item>
    <key>Casi particolari</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_item>
    <key>Codice Stato estero</key>
    <value></value>
  </field_item>
  <field_heading level="2">C1</field_heading>
  <field_item>
    <marker>1</marker>
    <key>TIPO</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <key>INDETERMINATO/DETERMINATO</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_item>
    <marker>3</marker>
    <key>REDDITO (punti 1,2,3 CU 2025)</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>4</marker>
    <key>ALTRI DATI</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_heading level="2">C2</field_heading>
  <field_item>
    <marker>1</marker>
    <key>TIPO</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <key>INDETERMINATO/DETERMINATO</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_item>
    <marker>3</marker>
    <key>REDDITO (punti 1,2,3 CU 2025)</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>4</marker>
    <key>ALTRI DATI</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_heading level="2">C3</field_heading>
  <field_item>
    <marker>1</marker>
    <key>TIPO</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <key>INDETERMINATO/DETERMINATO</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_item>
    <marker>3</marker>
    <key>REDDITO (punti 1,2,3 CU 2025)</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>4</marker>
    <key>ALTRI DATI</key>
    <checkbox class="unselected"/>
  </field_item>
  <field_heading level="2">C4</field_heading>
  <field_item>
    <marker>1</marker>
    <key>TIPOLOGIA LIMITE</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>2</marker>
    <key>SOMME A TASSAZIONE ORDINARIA</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>3</marker>
    <key>SOMME A IMPOSTA SOSTITUTIVA</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>4</marker>
    <key>RITENUTE IMPOSTA SOSTITUTIVA</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>5</marker>
    <key>BENEFIT</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>6</marker>
    <key>BENEFIT A TASSAZIONE ORDINARIA</key>
    <value>,00</value>
  </field_item>
  <field_item>
    <marker>7</marker>
    <key>TASSAZIONE ORDINARIA</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>8</marker>
    <key>TASSAZIONE SOSTITUTIVA</key>
    <value></value>
  </field_item>
  <field_item>
    <marker>9</marker>
    <key>ASSENZA REQUISITI</key>
    <value></value>
  </field_item>
</field_region>

```

```

</field_item>
<field_item>
  <marker>3</marker>
  <key>REDDITO (punti 1,2,3 CU 2025)</key>
  <value>,00</value>
</field_item>
...

```

</td><td style="vertical-align: top;">

```

...
<field_item>
  <marker>4</marker>
  <key>ALTRI DATI</key>
  <checkbox class="unselected"/>
</field_item>
<field_heading level="2">C3</field_heading>
<field_item>
  <marker>1</marker>
  <key>TIPO</key>
  <value></value>
</field_item>
<field_item>
  <marker>2</marker>
  <key>INDETERMINATO/DETERMINATO</key>
  <checkbox class="unselected"/>
</field_item>
<field_item>
  <marker>3</marker>
  <key>REDDITO (punti 1,2,3 CU 2025)</key>
  <value>,00</value>
</field_item>
<field_item>
  <marker>4</marker>
  <key>ALTRI DATI</key>
  <checkbox class="unselected"/>
</field_item>
<field_heading level="2">C4</field_heading>
<field_heading level="3">SOMME PER PREMI...
</field_heading>
<field_item>
  <marker>1</marker>
  <key>TIPOLOGIA LIMITE</key>
  <checkbox class="unselected"/>
</field_item>
<field_item>
  <marker>2</marker>
  <key>SOMME A TASSAZIONE ORDINARIA</key>
  <value>,00</value>
</field_item>
<field_item>
  <marker>3</marker>
  <key>SOMME A IMPOSTA SOSTITUTIVA</key>

```

```

        <value>,00</value>
      </field_item>
      ...
    </field_region>

```

```

</td></tr></table>

```

Middle section of a form with A and B choices

Nom _____ Prénom _____ Adresse _____ Bât. _____ Esc. _____ Étage _____ Tél. _____ STE D'ASSURANCES _____ Contrat n° _____ Nom, adresse de l'agent ou courtier _____ _____ _____ Tél. _____ ÊTES-VOUS DANS : ♦ un immeuble locatif : propriétaire ☐ occupant ☐ ♦ un immeuble en copropriété : copropriétaire : occupant ☐ non occupant ☐ locataire de copropriétaire ☐ ♦ une maison particulière : propriétaire ☐ occupant ☐	A ↓	B ↓	Nom _____ Prénom _____ Adresse _____ Bât. _____ Esc. _____ Étage _____ Tél. _____ STE D'ASSURANCES _____ Contrat n° _____ Nom, adresse de l'agent ou courtier _____ _____ _____ Tél. _____ ÊTES-VOUS DANS : ♦ un immeuble locatif : propriétaire ☐ occupant ☐ ♦ un immeuble en copropriété : copropriétaire : occupant ☐ non occupant ☐ locataire de copropriétaire ☐ ♦ une maison particulière : propriétaire ☐ occupant ☐			
COCHER LES CASES CONCERNÉES						
<table border="0" style="width: 100%;"> <tr> <td style="width: 33%; vertical-align: top;"> ☐ oui La cause du sinistre se situe-t-elle chez vous ? ☐ non </td> <td style="width: 33%; vertical-align: top;"> ☐ oui Êtes-vous assuré en dégâts des eaux ? ☐ non </td> <td style="width: 33%; vertical-align: top;"> ☐ oui Si vous êtes occupant et que vous allez déménager avez-vous donné ou reçu congé ? avant le sinistre après le sinistre ☐ </td> </tr> </table>				☐ oui La cause du sinistre se situe-t-elle chez vous ? ☐ non	☐ oui Êtes-vous assuré en dégâts des eaux ? ☐ non	☐ oui Si vous êtes occupant et que vous allez déménager avez-vous donné ou reçu congé ? avant le sinistre après le sinistre ☐
☐ oui La cause du sinistre se situe-t-elle chez vous ? ☐ non	☐ oui Êtes-vous assuré en dégâts des eaux ? ☐ non	☐ oui Si vous êtes occupant et que vous allez déménager avez-vous donné ou reçu congé ? avant le sinistre après le sinistre ☐				
NATURE DES DOMMAGES peinture et/ou papier peint						
<table border="0" style="width: 100%;"> <tr> <td style="width: 33%; vertical-align: top;"> ☐ collés ☐ agrafés ou cloués </td> <td style="width: 33%; vertical-align: top;"> { revêtements (sol, mur, plafond) } </td> <td style="width: 33%; vertical-align: top;"> ☐ collés ☐ agrafés ou cloués </td> </tr> </table>				☐ collés ☐ agrafés ou cloués	{ revêtements (sol, mur, plafond) }	☐ collés ☐ agrafés ou cloués
☐ collés ☐ agrafés ou cloués	{ revêtements (sol, mur, plafond) }	☐ collés ☐ agrafés ou cloués				
<table border="0" style="width: 100%;"> <tr> <td style="width: 33%; vertical-align: top;"> ☐ oui Ces aménagements ont-ils été exécutés à vos frais ? ☐ non </td> <td style="width: 33%; vertical-align: top;"> ☐ oui Autres dommages immobiliers (carrelage, parquet, plâtrerie...) ☐ Objets mobiliers ☐ Matériels ou marchandises </td> <td style="width: 33%; vertical-align: top;"> ☐ oui Autres dommages (à préciser) ☐ </td> </tr> </table>				☐ oui Ces aménagements ont-ils été exécutés à vos frais ? ☐ non	☐ oui Autres dommages immobiliers (carrelage, parquet, plâtrerie...) ☐ Objets mobiliers ☐ Matériels ou marchandises	☐ oui Autres dommages (à préciser) ☐
☐ oui Ces aménagements ont-ils été exécutés à vos frais ? ☐ non	☐ oui Autres dommages immobiliers (carrelage, parquet, plâtrerie...) ☐ Objets mobiliers ☐ Matériels ou marchandises	☐ oui Autres dommages (à préciser) ☐				
NOM DU GÉRANT ou du SYNDIC (à défaut du propriétaire) de l'IMMEUBLE _____ Adresse _____ Sté d'Assurances garantissant l'immeuble en dégâts des eaux : _____ _____ _____ Contrat n° _____ Nom, adresse de l'agent ou courtier _____ _____ _____ Tél. _____		NOM DU GÉRANT ou du SYNDIC (à défaut du propriétaire) de l'IMMEUBLE _____ Adresse _____ Sté d'Assurances garantissant l'immeuble en dégâts des eaux : _____ _____ _____ Contrat n° _____ Nom, adresse de l'agent ou courtier _____ _____ _____ Tél. _____				
OBSERVATIONS A :		OBSERVATIONS B :				
FAIT À A		LE B Signatures				

```

<field_region>
  <field_heading>COCHER LES CASES CONCERNEES</field_heading>
  <field_item>
    <key>La cause du sinistre se situe-t-elle chez vous ?</key>
    <text><checkbox class="unselected"/><marker>A</marker>oui</text>
    <text><checkbox class="unselected"/><marker>A</marker>non</text>
    <text><checkbox class="unselected"/><marker>B</marker>oui</text>
    <text><checkbox class="unselected"/><marker>B</marker>non</text>
  </field_item>
  <field_item>
    <key>Êtes-vous assuré en dégâts des eaux ?</key>
    <text><checkbox class="unselected"/><marker>A</marker>oui</text>
    <text><checkbox class="unselected"/><marker>A</marker>non</text>
    <text><checkbox class="unselected"/><marker>B</marker>oui</text>
    <text><checkbox class="unselected"/><marker>B</marker>non</text>
  </field_item>
</field_region>

```

```

    <key>Si vous êtes occupant et que vous allez déménager avez-vous donné ou
    reçu congé ?</key>
    <text><checkbox class="unselected"/><marker>A</marker>avant le
    sinistre</text>
    <text><checkbox class="unselected"/><marker>A</marker>après le
    sinistre</text>
    <text><checkbox class="unselected"/><marker>B</marker>avant le
    sinistre</text>
    <text><checkbox class="unselected"/><marker>B</marker>après le
    sinistre</text>
  </field_item>
  <field_heading>NATURE DES DOMMAGES peinture et/ou papier peint</field_heading>
  <field_item>
    <key>revêtements (sol, mur, plafond)</key>
    <text><checkbox class="unselected"/><marker>A</marker>collés</text>
    <text><checkbox class="unselected"/><marker>A</marker>agrafés ou
    cloués</text>
    <text><checkbox class="unselected"/><marker>B</marker>collés</text>
    <text><checkbox class="unselected"/><marker>B</marker>agrafés ou
    cloués</text>
  </field_item>
  <field_item>
    <key>Ces aménagements ont-ils été exécutés à vos frais ?</key>
    <text><checkbox class="unselected"/><marker>A</marker>oui</text>
    <text><checkbox class="unselected"/><marker>A</marker>non</text>
    <text><checkbox class="unselected"/><marker>B</marker>oui</text>
    <text><checkbox class="unselected"/><marker>B</marker>non</text>
  </field_item>
  <field_item>
    <key>Autres dommages immobiliers (carrelage, parquet, plâtrerie...)</key>
    <text><checkbox class="unselected"/><marker>A</marker></text>
    <text><checkbox class="unselected"/><marker>B</marker></text>
  </field_item>
  <field_item>
    <key>Objets mobiliers</key>
    <text><checkbox class="unselected"/><marker>A</marker></text>
    <text><checkbox class="unselected"/><marker>B</marker></text>
  </field_item>
  <field_item>
    <key>Matériels ou marchandises</key>
    <text><checkbox class="unselected"/><marker>A</marker></text>
    <text><checkbox class="unselected"/><marker>B</marker></text>
  </field_item>
  <field_item>
    <key>Autres dommages</key>
    <value><marker>A</marker><hint>(à préciser)</hint></value>
    <value><marker>B</marker><hint>(à préciser)</hint></value>
  </field_item>
</field_region>

```

Tabular form with strong 2D value relationship

Beiträge zur Altersvorsorge				52
		Steuerpflichtige Person / Ehemann / Person A		Ehefrau / Person B
		EUR		EUR
4	Arbeitnehmeranteil laut Nr. 23 a / b der Lohnsteuerbescheinigung	300		400
5	Beiträge zur landwirtschaftlichen Alterskasse; zu berufsständischen Versorgungseinrichtungen, die den gesetzlichen Rentenversicherungen vergleichbare Leistungen erbringen (abzüglich steuerfreier Zuschüsse laut Nr. 22 b der Lohnsteuerbescheinigung) – ohne Beiträge, die in Zeile 4 geltend gemacht werden –	301		401
6	Beiträge zu gesetzlichen Rentenversicherungen – ohne Beiträge, die in Zeile 4 geltend gemacht werden –	302		402
7	Erstattete Beiträge und / oder steuerfreie Zuschüsse zu den Zeilen 4 bis 6 (ohne Zuschüsse, die von den Beiträgen laut Zeile 8 abzuziehen sind und ohne Zuschüsse laut den Zeilen 9 und 10)	309		409

```

<field_region>
  <table>
    <srow/><text>Beiträge zur Altersvorsorge</text>
  <srow/>
  <srow/><text>52</text>
  <ecel/>
  <ecel/>
  <ched/><text>Steuerpflichtige Person / Ehemann / Person A</text>
  <ched/><text>Ehefrau / Person B</text>
  <ecel/>
  <fcel/><text>Arbeitnehmeranteil laut Nr. 23 a / b der Lohnsteuerbescheinigung</text>
  <fcel/><text>*FORM1*, -</text>
  <fcel/><text>*FORM2*, -</text>
  <fcel/><text>Beiträge zur landwirtschaftlichen Alterskasse; zu berufsständ...</text>
  <fcel/><text>*FORM3*, -</text>
  <fcel/><text>*FORM4*, -</text>
  <fcel/><text>Beiträge zu gesetzlichen Rentenversicherungen...</text>
  <fcel/><text>*FORM5*, -</text>
  <fcel/><text>*FORM6*, -</text>
  <fcel/><text>Erstattete Beiträge und / oder steuerfreie Zuschüsse zu den...</text>
  <fcel/><text>*FORM7*, -</text>
  <fcel/><text>*FORM8*, -</text>
  ...
  </table>
</field_region>
...
*FORMS referred above:
*FORM1*: <field_item><key>300</key><value></value><hint>EUR</hint></field_item>
*FORM2*: <field_item><key>400</key><value></value><hint>EUR</hint></field_item>
*FORM4*: <field_item><key>401</key><value></value></field_item>
*FORM5*: <field_item><key>302</key><value></value></field_item>
*FORM3*: <field_item><key>301</key><value></value></field_item>
*FORM6*: <field_item><key>402</key><value></value></field_item>
*FORM7*: <field_item><key>309</key><value></value></field_item>
*FORM8*: <field_item><key>409</key><value></value></field_item>

```

Mix table and form elements

Part III		Figure Your Credit	
10	If you checked (in Part I): Box 1, 2, 4, or 7 \$5,000 Box 3, 5, or 6 \$7,500 Box 8 or 9 \$3,750	Enter: }	10
Did you check box 2, 4, 5, 6, or 9 in Part I? Yes. You must complete line 11. No. Enter the amount from line 10 on line 12 and go to line 13.			
11	If you checked (in Part I): • Box 6, add \$5,000 to the taxable disability income of the spouse who was under age 65. Enter the total. • Box 2, 4, or 9, enter your taxable disability income. • Box 5, add your taxable disability income to your spouse's taxable disability income. Enter the total.	}	11 *
TIP For more details on what to include on line 11, see Figure Your Credit in the instructions.			
12	If you completed line 11, enter the smaller of line 10 or line 11. All others , enter the amount from line 10		12 74,992

```
...
<heading>Part III</heading>
<text>Figure Your Credit</text>
<text>10</text>
<table>
  <ched/><text>If you checked (in Part I):</text><ched/><text>Enter</text><nl>
  <fcel/><text>Box 1, 2, 4, or 7</text><fcel/><text>$5,000</text><nl>
  <fcel/><text>Box 3, 5, or 6</text><fcel/><text>$7,500</text><nl>
  <fcel/><text>Box 8 or 9</text><fcel/><text>$3,750</text><nl>
</table>
<field_region><field_item><key>10</key><value></value></field_item></field_region>
<text>11 If you checked (in Part I):</text>
<list class="unordered">
  <ldiv/>
  <text>Box 6, add $5,000 to the taxable...</text>
  <ldiv/>
  <text>Box 2, 4, or 9, enter your taxable...</text>
  <ldiv/>
  <text>Box 5, add your taxable disabilit...</text>
</list>
<field_region><field_item><key>11</key><value>.</value></field_item></field_region>
<picture><label value="logo"/></picture>
<text>For more details on what to include on line 11...</text>
<text>12 If you completed line 11, enter the smaller...</text>

<field_region><field_item><key>12</key><value>74,992</value></field_item></field_region>
>
...
```


16. Learning Disabilities and Autism

Population Profile

We support in the region of 680 people with a learning disability through social care. 192 of those live in residential care, a proportion higher than in other areas. The number of people with a learning disability is expected to rise by 30 people each year as life expectancy rises and a larger number of young people become the responsibility of adult social care each year.

Swindon has a higher number of people with a learning disability living in residential care and high costs supported housing. Our analysis of social work assessments and plans has also found that there is a need to be outcome and progression focused so that people learn new skills. A pilot has been undertaken with Wiltshire, with consultant Alder, on the implementation of progression planning.

How "Progression" fits with the budget (2)



Key to this work has been the higher quality of life, through delivery of sustainable outcomes, and also lower cost packages. With both of these comes the opportunity to innovate across the market.

Population Projection	2015	2020	2025	2030
People aged 18-64 predicted to have a learning disability	3,344	3,451	3,529	3,585
People aged 65+ predicted to have a learning disability	687	797	923	1087

Source: www.pansi.org.uk and www.poppi.org.uk (based on national not local population projections).

```

...
<field_region>
  <field_item>
    <key>Source</key>
    <value>www.pansi.org.uk and ... projections).</value>
  </field_item>
</field_region>
...

```

Detailed examples can be seen here: [Form Examples](#)

Split structure

We can capture content that is split (e.g. across columns or across pages) using the `<thread thread_id="N"/>` element, where N is a unique identifier.

The basic structure is shown below, e.g. for a `text` tag:

```

<text>
  <thread thread_id="1"/>
  This text item starts here
</text>
...
<text>
  <thread thread_id="1"/>
  and continues here.
</text>

```

Cross-column structure example

```

```

Each block that has location information is a top-level tag of the corresponding label, e.g. "text".

Elements which belong to the same document component must have the same thread ID and same host element type (e.g. all under `<text>`, not mixed `<text>` and `<picture>`).

```

<!-- ... -->
<text>
  <thread thread_id="1"/>
  <location value="10"/><location value="20"/>
  <location value="30"/><location value="40"/>
  where  $\tau_{x,y,z}$  are the Pauli matrices acting
  on Nambu space. We consider a circular-shaped boundary, the nor-
</text>

<picture>
  <caption>
    <location value="20"/><location value="30"/>
    <location value="40"/><location value="50"/>
    FIG. 3. The modules of the inner product of two MES spinors
  <formula><!-- ... --></formula>
  <!-- ... -->

```


```

</caption>
<!-- ... -->
</picture>

<text>
  <thread thread_id="1"/>
  <location value="30"/><location value="40"/>
  <location value="50"/><location value="60"/>
  mal direction of the boundary tangent for arbitrary angle  $\theta$  is
  <formula><!-- ... --></formula>
  <!-- ... -->
</text>

```

Cross-page structure example



The scenario in the above figure is represented as follows:

```

...
<text>
  <location value="10"/><location value="20"/>
  <location value="30"/><location value="40"/>
  <![CDATA[Our multi-faceted DE&I program includes the following initiatives:]]>
</text>

<list class="unordered">
  <thread thread_id="1"/>
  <ldiv/>
  <text>
    <location value="15"/><location value="25"/>
    <location value="35"/><location value="45"/>
    Mentorships and internship programs featuring diverse employees and students
  </text>
...

```

```

</div>
<text>
  <location value="20"/><location value="30"/>
  <location value="40"/><location value="50"/>
  Build Science, Technology, Engineering and Mathematics (STEM) employee
candidate pipeline via involvement with:
  <list class="unordered">
    </div>
    <text>
      <location value="25"/><location value="35"/>
      <location value="45"/><location value="55"/>
      Historically Black Colleges and Universities (HBCUs) site visits and
career fairs
    </text>
    ...
  </div>
  <text>
    <location value="30"/><location value="40"/>
    <location value="50"/><location value="60"/>
    San Diego Squared (STEM-focused nonprofit organization connecting
underrepresented student to the power
    of STEM by providing access to education, mentorship and resources to
develop STEM careers)
  </text>
  <list>
</text>
</list>

<page_footer>
  <location value="35"/><location value="45"/>
  <location value="55"/><location value="65"/>
  16 Neurocrine Biosciences
</page_footer>

<page_break/>

<list class="unordered">
  <thread thread_id="1"/>
  </div>
  <text>
    <location value="40"/><location value="50"/>
    <location value="60"/><location value="70"/>
    <![CDATA[Build upon DE&I employee education initiatives including: ...]]>
  </text>
  ...
</list>
...

```

References

Cross-references

Cross-references can be captured using the `<xref>` element as part of the element head, for pointing to a thread based on the `thread_id`.

Inline cross-reference example




Figure 3: Corpus Conversion Service annotation user interface. The PDF page is shown in the background, with overlaid text-cells (in darker shades). The annotation boxes can be drawn by dragging a rectangle over each segment with the respective label from the palette on the right.

include publication repositories such as arXiv³, government offices, company websites as well as data directory services for financial reports and patents. Scanned documents were excluded wherever possible because they can be rotated or skewed. This would not allow us to perform annotation with rectangular bounding-boxes and therefore complicate the annotation process.

Preparation work included uploading and parsing the sourced PDF documents in the Corpus Conversion Service (CCS) [22], a cloud-native platform which provides a visual annotation interface and allows for dataset inspection and analysis. The annotation interface of CCS is shown in Figure 3. The desired balance of pages between the different document categories was achieved by selective subsampling of pages with certain desired properties. For example, we made sure to include the title page of each document and bias the remaining page selection to those with figures or tables. The latter was achieved by leveraging pre-trained object detection models from PubLayNet, which helped us estimate how many figures and tables a given page contains.

Phase 2: Label selection and guideline. We reviewed the collected documents and identified the most common structural features they exhibit. This was achieved by identifying recurrent layout elements and lead us to the definition of 11 distinct class labels. These 11 class labels are *Caption*, *Footnote*, *Formula*, *List-item*, *Page-footer*, *Page-header*, *Picture*, *Section-header*, *Table*, *Text*, and *Title*. Critical factors that were considered for the choice of these class labels were (1) the overall occurrence of the label, (2) the specificity of the label, (3) recognisability on a single page (i.e. no need for context from previous or next page) and (4) overall coverage of the

```
<picture>
  <thread thread_id="1"/>
  <!--...-->
</picture>
<!--...-->
<text>
  <content>... is shown in </content>
  <text><xref thread_id="1"/>Figure 3</text>
  . The desired balance...
</text>
```

Hyperlinks

Hyperlinks can be captured using the `<href>` element as part of the element head, for pointing to a URI.

Basic example:

```
<text>
  <content>Visit our </content>
  <text><href uri="https://www.example.com"/>website</text>
  <content> for more information.</content>
</text>
```

Hyperink from a non-text element:

```
<text>Click on the image below:</text>
<picture>
  <href uri="https://www.example.com"/> <!-- the target URI -->
  <src uri="https://www.example.com/image.jpg"/> <!-- the image source URI -->
</picture>
```

Formatting

Formatting may be preserved through nested tags or escape sequences:

- Bold, italic, underline, strikethrough, handwriting
- Superscript, subscript
- Text direction markers

Examples of basic formatting:

```
<text>
  This text contains <bold>bold</bold>, <italic>italic</italic>,
  <underline>underlined</underline>, and <strikethrough>struck-through</strikethrough>
  text.
</text>
```

Nested formatting:

```
<text>
  You can combine <bold><italic>bold and italic</italic></bold> or
  <underline><bold>underlined and bold</bold></underline> text.
</text>
```

Handwriting formatting (for handwritten annotations or text):

```
<text>
  The printed text says "Sign here:" followed by
  <handwriting>John Smith</handwriting> in handwritten form.
</text>
```

Superscript and subscript:

```
<text>
  1<superscript>st</superscript> question: What is the formula for water?
  Answer: H<subscript>2</subscript>O.
</text>
```

Page Break with Continuation

Page breaks are complex components that interrupt the flow of a document. They can interrupt paragraphs, tables, lists, etc. In general, we follow two rules,

3. If content spans across one (or more) page breaks, add `<thread thread_id="N"/>` to each fragment, reusing the same `thread_id`.

4. For the follow up content of the page, we follow a reading order and close all open elements before the `<page_break/>` element is introduced.

An easy example is below,

```
<doclang>
  <text><thread thread_id="1"/>This paragraph spans across</text>
  <caption>Some caption</caption>
  <page_break/>
  <text><thread thread_id="1"/>multiple pages.</text>
</doclang>
```

Often, we have more complicated page breaks, in which a (nested) list is split across pages and further interrupted by other semantic elements (think page footers). In this case, we demand that all elements of the first page are added and/or closed **before** the page break and then opened again in the appropriate way after the page break, with the intent that the content in between the page breaks is a valid DocLang tree.

A more complicated example is shown below in which we break the content of a list-item,

```
<doclang>
  <list class="ordered">
    <thread thread_id="1"/>
    <ldiv/>
    <text>First item</text>
    <ldiv/>
    <text><thread thread_id="2"/>Second </text>
    ...
  </list>
  <page_footer>...</page_footer>
  <page_break/>
  <list class="ordered">
    <thread thread_id="1"/>
    <ldiv/>
    <text><thread thread_id="2"/>item</text>
  </list>
  ...
</doclang>
```

Above, `<thread thread_id="1"/>` captures that the list itself is split, while `<thread thread_id="2"/>` captures that a particular list item is split.

Custom vocabularies

The examples below illustrate custom vocabulary use, namely for capturing a chemistry picture in SMILES representation.

For details, see custom metadata and vocabulary guidelines in Appendix B: Recommendations.

For shared/interoperable documents, using a formal XML namespace is recommended:

```
<picture>
  <label value="chemistry_structure"/>
  <custom xmlns:acme="https://example.com/ns/doclang/custom/chemistry/1">
    <acme:smiles>C1=CC=C(C=C1)C(=O)O</acme:smiles>
  </custom>
  <src uri="molecule.svg"/>
</picture>
```

For local/private usage where formal namespaces are not used, a collision-resistant project prefix can be used:

```
<picture>
  <label value="chemistry_structure"/>
  <custom>
    <acme_smiles>C1=CC=C(C=C1)C(=O)O</acme_smiles>
  </custom>
  <src uri="molecule.svg"/>
</picture>
```

Bibliography

5. SmolDocling: An ultra-compact vision-language model for end-to-end multi-modal document conversion
6. Optimized Table Tokenization for Table Structure Recognition
7. DoclingDocument API Specification
8. W3C XML 1.0 Specification (Fifth Edition)
9. W3C HTML5 Specification
10. ISO 32000-2:2020 (PDF 2.0)
11. ISO 8601
12. Semantic Versioning 2.0.0 (semver.org)

Appendix A: Reference

Special Elements

This category comprises elements with specialized document-level function.

<doclang>

The document root element. Starts with an optional `<head>` followed by a sequence of applicable elements.

Allowed Context

Exists exactly once, as root element.

Attributes

Attribute	Required / Optional	Allowed Values	Description
xmlns	Optional; default: "https://www.doclang.ai/ns/v0"	{"https://www.doclang.ai/ns/v0"}	The DocLang specification version namespace.
version	Optional; default: "0.5"	{"0.5"}	The DocLang specification version the document is supposed to validate against, in "MAJOR.MINOR" format, i.e. first two positions of Semantic Versioning.

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Not allowed
Primary semantic elements	Allowed

Example

```
<doclang>  
  <!-- content -->  
</doclang>
```

<head>

Includes doc-level metadata.

Allowed Context

Can only be first child of `<doclang>`.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Not allowed
Primary semantic elements	Not allowed

`<page_break>`

Indicates a page break. A paginated document may be divided into pages using the `<page_break/>` empty element. Any page content, as split by `<page_break/>`, forms a valid DocLang document body, i.e. would be a valid DocLang document if wrapped in a `doclang` root element.

Allowed Context

Can only be child of `<doclang>`.

Attributes

None

Allowed Content Types

None (empty element).

Example

```
<doclang>
  <!-- first page content -->
  <page_break/>
  <!-- second page content -->
</doclang>
```

Semantic Elements

Semantic elements capture core components with specific meaning and functional role in the document (e.g. a paragraph, a table, a list etc.) and may optionally begin with a element head. They are generally meant to be interpreted as block-level elements (although they can also be inlined via nesting). Semantic elements that can appear on the top level within `<doclang>` are called *primary*, while those that can only appear within other semantic elements are called *secondary*.

`<text>`

Represents a piece of cohesive text as that would appear in a paragraph. Note: a special construct related to this element is the so-called "virtual `<text>`", which can occur only as a list item or a table cell — see `<list>` and `<table>` below for details.

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<heading>

Allowed Context

Any context that allows semantic elements.

Attributes

Attribute	Required / Optional	Allowed Values	Description
level	Optional; default "1"	Positive integer	

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<footnote>

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<page_header>

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<page_footer>

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<field_region>

Serves for scoping of field items, for example encapsulating a whole form.

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Not allowed
Primary semantic elements	Allowed

<list>

Captures a list. List items are started by the respective structural elements (<ldiv>). A non-empty <list> element body must begin with such a structural element. A list item can be defined without a wrapping tag, i.e. as pure (optional) element head followed by raw text; this is called an "virtual <text>" and is handled exactly like a regular <text> element.

Allowed Context

Any context that allows semantic elements.

Attributes

Attribute	Required / Optional	Allowed Values	Description
class	Optional; default: "unordered"	{"unordered", "ordered"}	

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	TRUE, also on cell level in case of virtual <text>
Raw text	Only on cell level, in case of virtual <text>
Primary semantic elements	Allowed

<table>

Captures a table in an OTSL-based format. Table cells are started by the respective structural elements (<fcell> etc). A non-empty <table> element body must begin with such a structural element. A table cell can be defined without a wrapping tag, i.e. as pure (optional) element head followed by raw text; this is called an "virtual <text>" and is handled exactly like a regular <text> element.

Allowed Context

Any context that allows semantic elements. And additionally as the first element of the element body of <picture class="chart">.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	TRUE, also on cell level in case of virtual <text>
Raw text	Only on cell level, in case of virtual <text>
Primary semantic elements	Allowed

<index>

Captures an index, e.g. for a table of contents or glossary, in an OTSL-based format. Index cells are started by the respective structural elements (<fcell> etc). A non-empty <index> element body must begin with such a structural element. A cell can be defined without a wrapping tag, i.e. as pure (optional) element head followed by raw text; this is called an "virtual <text>" and is handled exactly like a regular <text> element.

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	TRUE, also on cell level in case of virtual <code><text></code>
Raw text	Only on cell level, in case of virtual <code><text></code>
Primary semantic elements	Allowed

`<formula>`

Raw LaTeX formula content, i.e. without any LaTeX-specific wrapping such as `$ ... $`, `$$ ... $$`, `\( ... \)`, `\[ ... \]`, `\begin{math} ... \end{math}` or `\begin{equation} ... \end{equation}`.

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Not allowed

`<code>`

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Not allowed

`<picture>`

Element body can generally only contain a `<src>`, for image bytes or reference. Additionally, in case of `<picture class="chart">` (and only then) the element body may contain a `<table>`, in which case it must begin with it.

Allowed Context

Any context that allows semantic elements.

Attributes

Attribute	Required / Optional	Allowed Values	Description
class	Optional; default: "undefined"	{"undefined", "chart"}	The picture type.

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Not allowed
Primary semantic elements	Not allowed (except <table> in case of <picture class="chart">)

<marker>

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<group>

Container for encapsulating multiple semantic elements.

Allowed Context

Any context that allows semantic elements.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Not allowed
Primary semantic elements	Allowed

<field_heading>

Allowed Context

Can only be descendant of <field_region>.

Attributes

Attribute	Required / Optional	Allowed Values	Description
level	Optional; default "1"	Positive integer	

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<field_item>

Scoping of a field key (optional) and any corresponding values.

Allowed Context

Can only be descendant of <field_region>.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Not allowed
Primary semantic elements	Allowed

<key>

The key of a field (may correspond to 0-N field values).

Allowed Context

Can only be descendant of <field_item>.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<value>

A value of a field (may correspond to 0 or 1 field key).

Allowed Context

Can only be descendant of <field_item>.

Attributes

Attribute	Required / Optional	Allowed Values	Description
class	Optional; default: "read_only"	{"read_only", "fillable"}	

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<hint>

A hint regarding a field.

Allowed Context

Can only be descendant of <field_region>.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

<caption>

Optional part of the element head for capturing an associated caption.

Allowed Context

Can only be part of the element head of a semantic element.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Allowed
Raw text	Allowed
Primary semantic elements	Allowed

Property Elements

Property elements are non-semantic elements that help define useful traits of a semantic element, forming the main building blocks of the element head. Property elements that can appear on the top level of the element head are called *primary*, while those that can only

appear within other property elements are called *secondary*. The various property elements are further specified in the following subsections.

<label>

Optional part of the element head; serves for providing a detailed label for the respective element.

Allowed Context

Can only be child of a semantic element.

Attributes

Attribute	Required / Optional	Allowed Values	Description
value	Optional; default: "undefined"	Different value domains may be recommended per host element (not to be validated).	A label for concretely specifying a subclass type for the host element.

Allowed Content Types

None (empty element).

<thread>

Optional part of the element head; serves for establishing a logical document component. This can be useful for capturing fragmented components, e.g. spanning multiple bounding boxes (e.g. cross-column) or pages, or for defining anchors for cross references. To capture a fragmented component, we define separate instances of the respective element and use a <thread> with the same `thread_id` attribute for all of them

Allowed Context

Can only be child of a semantic element.

Attributes

Attribute	Required / Optional	Allowed Values	Description
thread_id	Required	Positive integer	The ID of the thread. All <thread> elements that share a given <code>thread_id</code> must be under the same host element type (e.g. all under <text>, not mixed <text> and <picture>).

Allowed Content Types

None (empty element).

<xref>

Optional part of the element head; serves for capturing an outgoing cross-reference from this component.

Allowed Context

Can only be child of a semantic element. Mutually exclusive with <href>.

Attributes

Attribute	Required / Optional	Allowed Values	Description
thread_id	Required	Positive integer	The ID of the referenced thread. This must be defined by at least one <thread> in the document.

Allowed Content Types

None (empty element).

<href>

Optional part of the element head; serves for capturing a URI referenced by this component.

Allowed Context

Can only be child of a semantic element. Mutually exclusive with <xref>.

Attributes

Attribute	Required / Optional	Allowed Values	Description
uri	Required	URI	The URI of the referenced resource.

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Not allowed
Primary semantic elements	Not allowed

<custom>

Optional part of the element head; custom metadata, e.g. for application-specific purposes. See Appendix B: Recommendations for naming and namespacing guidance for custom vocabularies.

Allowed Context

Can only be child of a semantic element.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Not allowed
Primary semantic elements	Not allowed

<location>

Optional part of the element head; coordinate system is the top-left corner of the page. When present, appears in sequence of 4 <location> instances, representing x0, y0, x1, y1. The following must then hold: $x0_norm \leq x1_norm$ and $y0_norm \leq y1_norm$ (i.e. first top-left point then bottom-right point), whereby $*_norm$ is the respective coordinate normalized to its effective resolution.

Allowed Context

Can only be child of a semantic element.

Attributes

Attribute	Required / Optional	Allowed Values	Description
resolution	Optional; defaults to <code>default_resolution@width</code> or <code>default_resolution@height</code> depending on whether location refers to x or y, otherwise "512" if respective <code>default_resolution</code> not explicitly specified	Positive integer	Axis boundary (exclusive) for the respective <code>location@value</code> .
value	Required	Integer within <code>[0, location.resolution)</code>	Coordinate w.r.t. top-left corner.

Allowed Content Types

None (empty element).

<layer>

The conceptual layer of the host element in the document.

Allowed Context

Can only be child of a semantic element.

Attributes

Attribute	Required / Optional	Allowed Values	Description
value	Optional; default:	{"body",	The layer value:

"body"	"background", "furniture"}	"body" is for the document's main content, "background" is for watermarks and other background components, while "furniture" is the fallback for any supplementary components not contributing to the document's main content, such as navigation or decorations.
--------	-------------------------------	--

Allowed Content Types

None (empty element).

Payload Elements

Payload elements are low-level elements that help define the effective content of another element.

<src>

The image's source.

Allowed Context

Can only be child of `<picture>`.

Attributes

Attribute	Required / Optional	Allowed Values	Description
uri	Required	URI	The source URI. May use a <code>data:</code> URI (RFC 2397) with base64-encoded payload, e.g. <code>uri="data:image/png;base64,..."</code> . Relative URIs are allowed too, e.g. <code>uri="assets/chart.svg"</code> .

Allowed Content Types

None (empty element).

<checkbox>

Allowed Context

Any context that allows raw text content.

Attributes

Attribute	Required / Optional	Allowed Values	Description
class	Optional; default: "unselected"	{"unselected", "selected"}	

Allowed Content Types

None (empty element).

<content>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

Formatting Elements

Formatting elements modify the styling and presentation within semantic or other formatting elements.

<bold>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<italic>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<underline>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<striketrough>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<superscript>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
--------------	-----------------------

Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<subscript>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<handwriting>

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

<rtl>

Indicates right-to-left direction.

Allowed Context

Any context that allows raw text content.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Allowed
Primary semantic elements	Not allowed

Structural Elements

Structural elements define boundaries within explicitly structured components like tables and lists.

<fcel>

Indicates the beginning of a full / regular cell.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<ecel>

Indicates the beginning of an empty cell.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<ched>

Indicates the beginning of a column header cell.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<rhed>

Indicates the beginning of a row header cell.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<corn>

Indicates the beginning of a corner cell, typically the top-left header intersection.

Allowed Context

Can only be child of `<table>` or `<index>`

Attributes

None

Allowed Content Types

None (empty element).

<srow>

Indicates the beginning of a section row header.

Allowed Context

Can only be child of `<table>` or `<index>`

Attributes

None

Allowed Content Types

None (empty element).

<lcel>

Left-merge extension token; extends the previous cell horizontally (colspan continuation).

Allowed Context

Can only be child of `<table>` or `<index>`

Attributes

None

Allowed Content Types

None (empty element).

<ucel>

Upward-merge extension token; extends the cell above vertically (rowspan continuation)

Allowed Context

Can only be child of `<table>` or `<index>`

Attributes

None

Allowed Content Types

None (empty element).

<xcel>

Cross/combined span extension token; used where both horizontal and vertical spanning intersect.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<nl>

Denotes the end of a table row.

Allowed Context

Can only be child of <table> or <index>

Attributes

None

Allowed Content Types

None (empty element).

<ldiv>

Indicates the beginning of a list item. It can either be empty or contain a <marker>.

Allowed Context

Can only be child of <list>.

Attributes

None

Allowed Content Types

Content Type	Allowed / Not allowed
Element head	Not allowed
Raw text	Not allowed
Primary semantic elements	Only <marker>

Document Head Elements

This category comprises the document-level metadata elements that are the building blocks of `<head>`.

`<default_resolution>`

Defines the default resolution for the document.

Allowed Context

Can only be child of `<head>`.

Attributes

Attribute	Required / Optional	Allowed Values	Description
width	Optional; default "512"	Non-negative integer	Default document width in pixels.
height	Optional; default "512"	Non-negative integer	Default document height in pixels.

Allowed Content Types

None (empty element).

Appendix B: Recommendations

This appendix is informative and does not define conformance requirements.

Recommended labels

Pictures

For the `label.value` of `<picture>` elements, we recommend using the values defined below:

Context	Recommended values
<code><picture class="chart"></code>	bar_chart, box_plot, flow_chart, line_chart, pie_chart, scatter_plot
else, i.e. <code><picture class="undefined"></code> (default)	full_page_image, page_thumbnail, photograph, chemistry_structure, bar_code, icon, logo, qr_code, signature, stamp, engineering_drawing, screenshot_from_computer, screenshot_from_manual, geographical_map, topographical_map, calendar, crossword_puzzle, music

Additional special cases:

- `other`: use when the picture was examined but does not fit any of the recommended values from above (e.g. a chart that is not bar/box/flow/line/pie/scatter).
- `undefined`: use when classification has not been performed (default `label@value`).

Note: `picture@class="undefined"` (default picture type) and `label@value="undefined"` (unclassified subclass) are independent.

Code

For the `label.value` of `<code>` elements, we recommend using the values defined below:

Context	Recommended values
<code><code></code>	Linguist v9.5.0 language keys (e.g. Python)

Additional special cases:

- `other`: use when the code was examined but does not match any of the recommended values from above.
- `undefined`: use when classification has not been performed (default `label@value`).

Custom vocabulary naming and namespacing

Content inside `<custom>` is implementation-defined and not governed by this standard. To improve interoperability and reduce naming collisions, the following recommendations apply:

- Producers of shared custom vocabularies SHOULD use formal XML namespaces with stable namespace URIs.
- Processors SHOULD treat the namespace URI as the namespace identifier and MUST NOT assume semantic meaning from prefix names alone.
- For private or local use where formal namespaces are not used, producers SHOULD use collision-resistant element names prefixed with a stable organization or project identifier (e.g. `acme_`).
- Producers SHOULD avoid ambiguous generic names such as `item`, `meta`, or `data` unless these are clearly scoped by namespace or equivalent prefixing.
- Producers SHOULD document custom vocabularies (intended meaning, value domains, and versioning policy) when documents are shared across tools or organizations.

Token vocabulary

Below is a list of tokens that can be used for a DocLang-compliant tokenizer.

The token vocabulary trades off size and inference cost:

- For frequent elements such as `<location>` (often paired with semantic elements), the vocabulary defines one token per concrete instance — e.g. `<location value="0"/>`, `<location value="1"/>`, ..., `<location value="511"/>` — to reduce inference overhead.
- For rare elements such as `<thread>`, the vocabulary uses separate tokens — e.g. `<thread thread_id="the id, "/>` — to limit vocabulary growth at the cost of slightly more inference work.

Token	Description
<code><doclang></code>	doclang start
<code></doclang></code>	doclang end
<code><page_break/></code>	page_break
<code>"/></code>	end of self-closing element with attributes
<code><text></code>	text start
<code></text></code>	text end
<code><heading></code>	level-1 heading start
<code><heading level="2"></code>	level-2 heading start
<code><heading level="3"></code>	level-3 heading start
<code><heading level="4"></code>	level-4 heading start
<code><heading level="5"></code>	level-5 heading start
<code><heading level="6"></code>	level-6 heading start
<code></heading></code>	heading end

<footnote>	footnote start
</footnote>	footnote end
<page_header>	page_header start
</page_header>	page_header end
<page_footer>	page_footer start
</page_footer>	page_footer end
<field_region>	field_region start
</field_region>	field_region end
<list>	unordered list start
<list class="ordered">	ordered list start
</list>	list end
<table>	table start
</table>	table end
<index>	index start
</index>	index end
<formula>	formula start
</formula>	formula end
<code><label value="	start of code with label
</code>	code end
<picture><label value="	start of picture with label
<picture class="chart"><label value="	start of chart picture with label
</picture>	picture end
<marker>	marker start
</marker>	marker end
<group>	group start
</group>	group end
<field_heading>	level-1 field_heading start
<field_heading level="2">	level-2 field_heading start
<field_heading level="3">	level-3 field_heading start
<field_heading level="4">	level-4 field_heading start
<field_heading level="5">	level-5 field_heading start
<field_heading level="6">	level-6 field_heading start
</field_heading>	field_heading end
<field_item>	field_item start
</field_item>	field_item end
<key>	key start
</key>	key end
<value>	read-only value start
<value class="fillable">	fillable value start
</value>	value end
<hint>	hint start
</hint>	hint end
<caption>	caption start
</caption>	caption end

<thread thread_id="	thread with thread_id attribute start
<xref thread_id="	xref with thread_id attribute start
<href uri="	href with uri attribute start
<custom>	custom start
</custom>	custom end
<smiles>	custom SMILES element start (should best be accordingly namespaced)
</smiles>	custom SMILES element end
<layer value="	layer with value attribute start
<src uri="	src with uri attribute start
<checkbox class="unselected"/>	unselected checkbox
<checkbox class="selected"/>	selected checkbox
<content>	content start
</content>	content end
<![CDATA[	CDATA section start
]]>	CDATA section end
<bold>	bold start
</bold>	bold end
<italic>	italic start
</italic>	italic end
<underline>	underline start
</underline>	underline end
<strikethrough>	strikethrough start
</strikethrough>	strikethrough end
<superscript>	superscript start
</superscript>	superscript end
<subscript>	subscript start
</subscript>	subscript end
<handwriting>	handwriting start
</handwriting>	handwriting end
<rtl>	rtl start
</rtl>	rtl end
<fcel/>	fcel
<ecel/>	ecel
<ched/>	ched
<rhed/>	rhed
<corn/>	corn
<srow/>	srow
<lcel/>	lcel
<ucel/>	ucel
<xcel/>	xcel
<nl/>	nl
<ldiv/>	lddiv
<ldiv><marker>	start of lddiv with marker
</marker></ldiv>	end of lddiv with marker

```
<location value="0"/>,<location value="1"/>,...,<location value="511"/>
```

location tokens with values from 0 to 511

Appendix C: Future Extensions

These features are considered for future versions of the standard.

Horizontal Threading

Horizontal threading enables linking related content across the horizontal axis in page or table layouts. The `h_thread` element supports this by explicitly connecting content (like table rows or columns) that spans multiple pages, ensuring these threads remain structured and traceable.

Metadata

`<head>`

Document-level metadata is contained in the optional `<head>` element.

Below we list the reserved core metadata elements to be used within `<head>`:

- `title`
- each `author` element can optionally begin with one or more `affiliation` elements
- `date`
- `page_size`, the actual page size. An element without the `page_no` attribute defines the default size for all pages, when `page_no` is specified it is counted from 1.
- `language`, Identifies the (human) language of the document, e.g., English, German, French, Spanish, Japanese. The content MUST be an ISO 639-3 language identifier. Optional attributes: `classifier` (the tool/method used, e.g., fastText) and `score` (confidence in [0, 1]). Multiple `language` entries MAY be provided.
- `generated_by`, upstream pipeline information, e.g. VLM ID
- `topic`, topic that the document is most likely to fall in such as Science and Technology, Legal, etc. The topics should preferably come from some taxonomy. Classifier defines the classifier used for classifying into the given topic and score is the confidence score of classifier and $0 \leq \text{Scores} \leq 1$. This can be one or more.
- `summary`, a summary of the document
- `document_hash`, Hash of the document, whereas `hash_function` defines the algorithm used to compute the hash, e.g., SHA2. This can be one or more.

Here is an example:

```
<doclang>
  <head>
    <!-- reserved elements -->
    <title>My Company's Annual Report</title>
    <author_info>
      <author>Author 1 Name</author>
      <author>
        <affiliation>Affiliation A</affiliation>
```

```

    <affiliation>Affiliation B</affiliation>
    Author 2 Name
  </author>
</author_info>
<date>2024-01-01</date>
<language classifier="fastText" score="0.7">eng</language>
<language classifier="fastText" score="0.2">spa</language>
<topic topic_taxonomy="taxonomy" score="0.5">Technology</topic>
<topic topic_taxonomy="taxonomy" score="0.5">Math</topic>
<document_hash
hash_function="sha256sum"/>75f2db0c6124527bf6dd48440f95fc864a5108d28517633f937923a7d819
9185</document_hash>
  <summary>This is a summary of the document</summary>
  <generated_by>example_vlm_org/example_vlm_name</generated_by>
  <default_resolution width="512" height="512"/>
  <page_size width="612" height="792"/>
  <page_size page_no="4" width="792" height="612"/>

  <!-- examples of custom elements -->
  <my_company_hap_filter_hate/>0.1</my_company_hap_filter_hate>
  <my_company_hap_filter_abuse/>0.1</my_company_hap_filter_abuse>
  <my_company_hap_filter_profanity/>0.1</my_company_hap_filter_profanity>
</head>
<!-- document content -->
</doclang>

```

Governance and compliance metadata

In addition to the core metadata elements, publishers can optionally provide metadata pertaining to governance and compliance. These elements allow the communication of acceptable use, policy, licensing, contact information and compliance requirements.

Governance and compliance metadata **MUST** be expressed at the document level inside `<head>` and **MAY** be overridden at component level for finer-grained control.

Standards reference and interpretation

The standards referenced throughout this Governance and Compliance section are provided to support alignment, interpretation, and interoperability. They are **informative**, not normative, unless explicitly stated otherwise.

These references are intended to:

- Clarify regulatory or industry concepts reflected by the metadata elements
- Assist implementers in mapping DocLang governance signals to existing compliance programs
- Avoid re-defining legal or regulatory obligations within this standard

DocLang governance metadata does **not** claim conformance to any listed framework by itself. Rather, it provides structured, machine-readable signals that downstream systems **MAY** use to support compliance, risk management, and audit workflows.

The following standards and regulations are commonly referenced:

Standard / Regulation	Scope and relevance
GDPR (EU General Data Protection Regulation)	Governs processing of personal data, including lawful basis, purpose limitation, data minimization, retention, data subject rights, and cross-border transfer obligations.
EU AI Act	Establishes obligations related to AI system risk categories, data governance, transparency, and human oversight for AI systems placed on or used within the EU.
ISO/IEC 27001	International standard for information security management systems (ISMS), covering access control, asset management, logging, and security controls.
ISO/IEC 27701	Extension to ISO/IEC 27001 focused on privacy information management (PIMS), including controller/processor roles and personal data handling.
ISO/IEC 23894	Guidance on AI risk management, including lifecycle governance, human oversight, and accountability for AI systems.
HIPAA	U.S. regulation governing protected health information (PHI), including privacy, security, and breach notification requirements.
PCI DSS	Security standard for handling payment card data, including storage, processing, and transmission controls.
FedRAMP	U.S. government program defining security requirements for cloud services used by federal agencies.

Where multiple standards are referenced for a single metadata element, the intent is to indicate conceptual alignment rather than impose cumulative obligations. Implementers SHOULD consult authoritative sources and legal counsel to determine applicability within their specific legal and regulatory context.

Governance narrative and flow

Governance metadata is intended to travel with the document and provide downstream systems with machine-readable constraints. The diagram below illustrates how the four governance areas map to common document-to-AI workflows.

```
flowchart LR
    D["Document content<br/>(DocLang body)"] --> H["<head><br/>Governance metadata"]
    H --> PII["Privacy & PII controls<br/>(pii_*)"]
    H --> EXT["Extraction controls<br/>(extraction_*)"]
    H --> RAG["RAG controls<br/>(rag_*)"]
```

```

H --> TRN["Training controls<br/>(training_*)"]

D --> X["Extraction pipeline"]
EXT --> X
PII --> X
X --> XD["Extracted dataset / fields"]

D --> I["Index/Embed pipeline"]
RAG --> I
PII --> I
I --> E["Embeddings / index"]

E --> Q["Retrieve"]
RAG --> Q
Q --> M["Model inference"]
M --> O["Output"]
RAG --> O
PII --> O

D --> T["Training / fine-tuning pipeline"]
TRN --> T
PII --> T
T --> TD["Training dataset"]
T --> TM["Trained model"]

```

Naming and terminology conventions

This section uses the following terminology consistently:

- **RAG** refers to retrieval-augmented generation workflows that embed/index content and retrieve it at inference time.
- **Extraction** refers to producing structured outputs (fields/records) derived from document content.
- **Training** refers to using content for model training, fine-tuning, evaluation, or benchmarking.
- **Artifacts** refers to derived outputs created by processing the document (e.g., extracted datasets, embeddings/indexes, caches, training datasets).

Where an element carries an enumerated value (e.g., `pii_status`, `rag_embedding_scope`), implementations SHOULD use a controlled vocabulary. Where an element carries a boolean, implementations SHOULD use explicit `true` / `false` values.

Governance overview

Governance metadata is intended to be machine-actionable: it should enable downstream systems (including AI systems) to determine what is permitted, under what constraints, and with what obligations.

Licensing and rights

- **licenses** Indicate one or more licenses covering use of the document.

Data classification and privacy posture

- **data_classification** One or more data classifications can be given for the document content.

In general, data classification is not globally standardized. Organizations usually define a classification system suitable for their respective mission. These elements allow an organization to classify document sensitivity in their own terms.

Acceptable use and purpose limitation

- **acceptable_use** Organizations may express acceptable use cases for the provided document data.

Stewardship and contact

- **stewardship** Provides the name of a person and/or organization with governance responsibility at the document owning organization.

Access control policy

- **access_policy** Provides the ability to express access policy as well as enumerate roles allowed to access the data.

Similar to data classification, there are no standards specifying role semantics. This element allows organizations to describe access policy and roles in their own terms.

Retention and deletion

- **retention_policy** Allows organizations to state retention objectives for the document data.

Compliance frameworks

- **compliance_requirements** States the compliance frameworks (regulatory or industrial) governing the lifecycle and use of the documents.

Privacy and PII controls

This subsection defines governance signals related to personal data detection, sensitivity, and permitted handling. Implementations SHOULD use these elements to drive privacy-aware processing (e.g., redaction, restricted access, minimization).

The following optional elements MAY be provided to describe personal data presence, sensitivity, permitted processing, and privacy-related obligations. Unless otherwise required by an implementation, these elements are intended to be expressed at the document level inside `<head>`.

Element	Purpose	Standards alignment (non-exhaustive)
pii_status	Indicates whether the document contains PII.	ISO 27701; ISO 27001 A.5/A.8;

		GDPR Art. 4(1), 5(1)
pii_sensitivity_level	Classifies the sensitivity level of detected PII.	ISO 27701; GDPR Art. 9–10
pii_source_type	Identifies the origin/source of PII (e.g., provided by user, derived, third-party).	GDPR Art. 13–14
controller_processor_role	Defines the organizational role for processing (controller/processor or equivalent).	GDPR Art. 24–28
pii_processing_purpose	Specifies the purpose of processing (purpose limitation).	GDPR Art. 5(1)(b), Art. 6
pii_lawful_basis	Records lawful basis for processing.	GDPR Art. 6(1)
special_category_condition	Condition for processing special-category data (if applicable).	GDPR Art. 9(2)
pii_minimisation_status	Indicates whether minimisation has been applied (data minimisation / privacy by design).	GDPR Art. 5(1)(c), Art. 25
pii_transformation_level	Indicates transformation applied to PII (e.g., redacted, masked, pseudonymized).	GDPR Recital 26; GDPR Art. 4(5)
reidentification_risk	Expresses assessed risk of re-identification where transformations are used.	ISO 27701; GDPR Recital 26
access_control_level	Required access tier/controls for handling this document.	ISO 27001 A.9; GDPR Art. 32
ai_use_restriction	Indicates allowed AI uses or prohibitions for this document's content.	GDPR Art. 5(1)(b–c)
cross_border_transfer_status	Indicates whether cross-border transfers occur/are allowed.	GDPR Art. 44–49
transfer_mechanism	Indicates transfer mechanism where applicable (e.g., adequacy, SCCs).	GDPR Art. 45–47
retention_category	Indicates retention category for personal data contained in the document.	GDPR Art. 5(1)(e)
dsr_impact_flag	Signals potential impact on data subject rights (DSR handling implications).	GDPR Art. 12–23

dpia_required	Indicates whether a DPIA is required for intended processing.	GDPR Art. 35–36
children_pii_present	Flags whether children’s data is present.	GDPR Art. 8
automated_decisioning_relevance	Indicates whether automated decision-making/profiling obligations apply.	GDPR Art. 22
logging_monitoring_enabled	Indicates whether logging/monitoring is enabled for access and processing (accountability/auditability).	ISO 27001 A.12/A.16; GDPR Art. 5(2)

Implementations SHOULD define controlled vocabularies (and, where applicable, boolean conventions) for these elements. If an organization already has established internal taxonomies for classification, purpose, lawful basis, access tiers, or transfer mechanisms, those SHOULD be used consistently.

Data extraction controls

This subsection defines governance signals that constrain automated extraction, transformation, and downstream use of extracted fields. Implementations SHOULD use these elements to ensure purpose limitation and auditability of extraction.

The following optional elements MAY be provided to express constraints and obligations related to automated or manual data extraction from the document. These elements are intended to guide downstream systems that perform field extraction, transformation, enrichment, or export. Unless otherwise required by an implementation, these elements SHOULD be expressed at the document level inside `<head>`, and MAY be overridden at component level for finer-grained control.

Element	Purpose	Standards alignment (non-exhaustive)
extraction_permitted	Indicates whether automated data extraction is permitted at all.	GDPR Art. 5(1)(a,b); ISO 27701
extraction_scope	Defines which parts or components of the document may be extracted (e.g., full document, tables only, specific sections).	GDPR Art. 5(1)(b,c)
extraction_purpose	Specifies the allowed purpose(s) for extracted data.	GDPR Art. 5(1)(b); ISO 27701

extraction_granularity	Indicates permitted level of granularity (e.g., aggregate only, field-level, record-level).	GDPR Art. 5(1)(c)
pii_extraction_allowed	Indicates whether PII may be included in extracted outputs.	GDPR Art. 6; ISO 27701
sensitive_data_extraction_allowed	Indicates whether special-category or sensitive data may be extracted.	GDPR Art. 9–10
extraction_transformation_required	Specifies required transformations during extraction (e.g., redaction, masking, pseudonymization).	GDPR Art. 25; Recital 26
extraction_output_constraints	Constrains allowed output formats or destinations for extracted data.	ISO 27001 A.8; GDPR Art. 32
downstream_sharing_permitted	Indicates whether extracted data may be shared with downstream systems or third parties.	GDPR Art. 5(1)(a,b); Art. 28
downstream_usage_restrictions	Specifies restrictions on how extracted data may be used downstream.	GDPR Art. 5(1)(b)
extraction_audit_required	Indicates whether extraction activities must be logged and auditable.	GDPR Art. 5(2); ISO 27001 A.12
extraction_audit_retention	Specifies retention period for extraction audit logs.	GDPR Art. 5(1)(e)
human_in_the_loop_required	Indicates whether human review/approval is required before or after extraction.	ISO 23894; ISO 27701
automated_decisioning_dependency	Indicates whether extracted data feeds automated decision-making systems.	GDPR Art. 22

Implementations SHOULD define controlled vocabularies for scope, purpose, granularity, transformations, and output constraints. Where extraction interacts with PII, these

elements SHOULD be interpreted in conjunction with the Privacy and PII controls defined above.

RAG and retrieval controls

This subsection defines governance signals that constrain whether and how document content may be embedded, indexed, chunked, retrieved, and presented to models during retrieval-augmented generation. Implementations SHOULD use these elements to control exposure, leakage risk, and attribution requirements.

The following optional elements MAY be provided to govern whether and how document content may be embedded, indexed, retrieved, and surfaced to models or users as part of retrieval-augmented generation (RAG) workflows. These elements are intended to control exposure risk, attribution, and downstream use of retrieved content. Unless otherwise required by an implementation, these elements SHOULD be expressed at the document level inside `<head>`, and MAY be overridden at component level for finer-grained control.

Element	Purpose	Standards alignment (non-exhaustive)
<code>rag_permitted</code>	Indicates whether the document may be used in RAG workflows at all.	GDPR Art. 5(1)(a,b); ISO 27701
<code>rag_indexing_allowed</code>	Indicates whether the document content may be indexed or embedded for retrieval.	GDPR Art. 5(1)(b,c); ISO 27001 A.8
<code>rag_embedding_scope</code>	Defines which parts or components of the document may be embedded (e.g., full document, summaries only, specific sections).	GDPR Art. 5(1)(b,c)
<code>rag_chunking_constraints</code>	Specifies constraints on chunking strategy (e.g., max size, boundaries, semantic-only).	ISO 23894; privacy-by-design principles
<code>rag_query_restrictions</code>	Defines restrictions on the types of queries that may retrieve this content.	GDPR Art. 5(1)(b)
<code>rag_output_attribution_required</code>	Indicates whether attribution or citation is required when content is retrieved	ISO 27001 A.18; copyright best practice

	or surfaced.	
rag_output_transformation_required	Specifies required transformations on retrieved content (e.g., summarization, redaction).	GDPR Art. 25; Recital 26
rag_pii_exposure_allowed	Indicates whether retrieved content may expose PII.	GDPR Art. 6; Art. 32
rag_sensitive_data_exposure_allowed	Indicates whether special-category or sensitive data may be exposed via retrieval.	GDPR Art. 9–10
rag_downstream_sharing_permitted	Indicates whether retrieved content may be shared beyond the immediate RAG response.	GDPR Art. 5(1)(a,b); Art. 28
rag_caching_allowed	Indicates whether retrieved content may be cached for performance or reuse.	ISO 27001 A.8; GDPR Art. 5(1)(e)
rag_cache_retention	Specifies retention period for cached embeddings or retrieved content.	GDPR Art. 5(1)(e)
rag_audit_required	Indicates whether retrieval events must be logged and auditable.	GDPR Art. 5(2); ISO 27001 A.12
rag_audit_retention	Specifies retention period for RAG access and retrieval logs.	GDPR Art. 5(1)(e)
rag_model_scope	Restricts which models or model classes may access this content via RAG.	ISO 23894; internal governance

Implementations SHOULD define controlled vocabularies for embedding scope, chunking constraints, query restrictions, and model scope. Where RAG interacts with PII or sensitive data, these elements SHOULD be interpreted in conjunction with the Privacy and PII controls defined above.

Document training controls

This subsection defines governance signals that constrain whether and how document content may be used for training, fine-tuning, or evaluation of models. Implementations

SHOULD use these elements to ensure licensing compliance, privacy protection, provenance tracking, and alignment with regulatory and contractual obligations.

The following optional elements MAY be provided to govern whether and how document content may be used for model training, fine-tuning, evaluation, or benchmarking. These elements are intended to ensure licensing compliance, privacy protection, provenance tracking, and alignment with regulatory and contractual obligations. Unless otherwise required by an implementation, these elements SHOULD be expressed at the document level inside `<head>`, and MAY be overridden at component level for finer-grained control.

Element	Purpose	Standards alignment (non-exhaustive)
training_permitted	Indicates whether the document may be used for any form of model training or fine-tuning.	GDPR Art. 5(1)(a,b); ISO 27701
training_scope	Defines which parts or components of the document may be used for training (e.g., full document, summaries only, specific sections).	GDPR Art. 5(1)(b,c)
training_purpose	Specifies the intended purpose of training (e.g., general models, domain-specific models, evaluation only).	GDPR Art. 5(1)(b)
training_model_type	Restricts the types or classes of models that may be trained using this content.	ISO 23894; internal governance
training_data_retention	Specifies retention period for training datasets derived from this document.	GDPR Art. 5(1)(e)
training_dataset_reuse_allowed	Indicates whether derived training datasets may be reused beyond the initial training purpose.	GDPR Art. 5(1)(b)
training_derivative_sharing_permitted	Indicates whether trained models or derivatives may be	GDPR Art. 28; licensing obligations

	shared with third parties.	
training_pii_included	Indicates whether training data may include PII.	GDPR Art. 6; ISO 27701
training_sensitive_data_included	Indicates whether special-category or sensitive data may be included in training.	GDPR Art. 9–10
training_transformation_required	Specifies required transformations prior to training (e.g., anonymization, pseudonymization).	GDPR Art. 25; Recital 26
training_provenance_required	Indicates whether provenance metadata must be retained for training records.	ISO 27001 A.12; AI accountability best practice
training_audit_required	Indicates whether training usage must be logged and auditable.	GDPR Art. 5(2); ISO 27001 A.12
training_audit_retention	Specifies retention period for training-related audit logs.	GDPR Art. 5(1)(e)
model_output_usage_constraints	Specifies constraints on use of models trained on this content (e.g., internal-only, non-commercial).	Licensing and IP best practice
right_to_be_forgotten_applicability	Indicates whether erasure obligations apply to trained models or datasets.	GDPR Art. 17; emerging AI guidance

Implementations SHOULD define controlled vocabularies for training scope, purpose, model type, and transformation requirements. Where training involves personal or sensitive data, these elements SHOULD be interpreted in conjunction with the Privacy and PII controls defined above.

Minimal and full governance profiles

Implementations may adopt either a minimal governance profile (recommended baseline) or a full governance profile (richer control surface). These profiles are informative and provided to encourage consistent adoption.

Minimal profile (recommended baseline)

Area	Recommended elements
------	----------------------

Licensing & compliance	licenses, compliance_requirements
Classification & access	data_classification, access_policy (or access_control_level where used), retention_policy
PII	pii_status, pii_sensitivity_level (when pii_status is present)
Extraction	extraction_permitted, pii_extraction_allowed
RAG	rag_permitted, rag_indexing_allowed, rag_pii_exposure_allowed
Training	training_permitted, training_pii_included

Full profile (expanded control surface)

The full profile includes the minimal profile plus additional elements from the PII, Extraction, RAG, and Training subsections to express:

- purpose limitation and lawful basis
- component-level scope constraints
- transformation requirements (redaction/masking/pseudonymization)
- caching/index retention and auditability
- model scope restrictions and provenance requirements

Producers SHOULD avoid emitting elements with ambiguous free-text values when a controlled vocabulary is available.

Example

Example use of the governance and compliance elements is shown below:

```
<doclang>
  <head>
    <!-- reserved elements -->
    <title>My Company's Annual Report</title>
    <author_info>
      <author>Author 1 Name</author>
    </author_info>
    <date>2024-01-01</date>
    <language classifier="fastText" score="0.7">eng</language>
    <topic topic_taxonomy="taxonomy" score="0.5">Technology</topic>
    <document_hash
hash_function="sha256sum"/>75f2db0c6124527bf6dd48440f95fc864a5108d28517633f937923a7d819
9185</document_hash>
    <summary>This is a summary of the document</summary>
    <generated_by>example_vlm_org/example_vlm_name</generated_by>

    <licenses>
      <license>https://www.apache.org/licenses/LICENSE-2.0</license>
    </licenses>
```

```
<data_classification>
  <data_class>confidential</data_class>
  <data_class>personal information</data_class>
</data_classification>

<acceptable_use>
  <purpose>General-purpose language models</purpose>
  <purpose>Sales and marketing</purpose>
</acceptable_use>

<stewardship>
  <steward>
    <name>Charles Owens</name>
    <contact>abc@some.org</contact>
    <org>Dataset Organization</org>
  </steward>
</stewardship>

<access_policy>
  <policy>
    <ref>http://www.some.org/policies/AC-2345</ref>
    <roles>
      <role>viewer</role>
      <role>reader</role>
    </roles>
  </policy>
</access_policy>

<retention_policy>
  <policy>
    <ref>http://www.some.org/policies/AC-2345</ref>
    <retention_period unit="year">5</retention_period>
    <deletion_method>permanent secure deletion</deletion_method>
    <documentation>record deletion event, date, method and personnel
responsible</documentation>
  </policy>
</retention_policy>

<compliance_requirements>
  <compliance_req>GDPR</compliance_req>
  <compliance_req>HIPAA</compliance_req>
  <compliance_req>FedRAMP</compliance_req>
  <compliance_req>PCI DSS</compliance_req>
  <compliance_req>EU AI Act</compliance_req>
</compliance_requirements>

</head>
<!-- document content -->
</doclang>
```

Consolidated example (PII + extraction + RAG + training)

The following example illustrates a single <head> that combines Privacy and PII controls, Data extraction controls, RAG and retrieval controls, and Document training controls. Implementations MAY choose to interpret these as organization-wide defaults for the document, and MAY override at component level for finer-grained control.

```
<doclang>
  <head>
    <!-- core metadata (illustrative) -->
    <title>Customer Support Case File</title>
    <date>2025-01-15</date>
    <language classifier="fastText" score="0.92">eng</language>
    <generated_by>example_pipeline/doc_ingest_v2</generated_by>

    <!-- licensing / classification / compliance (existing governance elements) -->
    <licenses>
      <license>https://www.apache.org/licenses/LICENSE-2.0</license>
    </licenses>

    <data_classification>
      <data_class>confidential</data_class>
      <data_class>personal information</data_class>
    </data_classification>

    <acceptable_use>
      <purpose>Customer support automation</purpose>
      <purpose>Internal analytics</purpose>
    </acceptable_use>

    <compliance_requirements>
      <compliance_req>GDPR</compliance_req>
      <compliance_req>ISO/IEC 27001</compliance_req>
      <compliance_req>ISO/IEC 27701</compliance_req>
    </compliance_requirements>

    <!-- Privacy and PII controls -->
    <pii_status>present</pii_status>
    <pii_sensitivity_level>medium</pii_sensitivity_level>
    <pii_source_type>user_provided</pii_source_type>
    <controller_processor_role>controller</controller_processor_role>
    <pii_processing_purpose>case_resolution</pii_processing_purpose>
    <pii_lawful_basis>legitimate_interest</pii_lawful_basis>
    <pii_minimisation_status>applied</pii_minimisation_status>
    <pii_transformation_level>pseudonymized</pii_transformation_level>
    <reidentification_risk>low</reidentification_risk>
    <access_control_level>restricted</access_control_level>
    <ai_use_restriction>no_general_training</ai_use_restriction>
    <cross_border_transfer_status>not_permitted</cross_border_transfer_status>
    <retention_category>support_case_records</retention_category>
    <dsr_impact_flag>true</dsr_impact_flag>
    <dpia_required>false</dpia_required>
    <logging_monitoring_enabled>true</logging_monitoring_enabled>
```

```

<!-- Data extraction controls -->
<extraction_permitted>true</extraction_permitted>
<extraction_scope>tables_and_forms_only</extraction_scope>
<extraction_purpose>case_metrics</extraction_purpose>
<extraction_granularity>field_level</extraction_granularity>
<pii_extraction_allowed>false</pii_extraction_allowed>
<sensitive_data_extraction_allowed>false</sensitive_data_extraction_allowed>
<extraction_transformation_required>redact</extraction_transformation_required>

<extraction_output_constraints>internal_systems_only</extraction_output_constraints>
  <downstream_sharing_permitted>false</downstream_sharing_permitted>
  <extraction_audit_required>true</extraction_audit_required>
  <extraction_audit_retention unit="day">90</extraction_audit_retention>
  <human_in_the_loop_required>true</human_in_the_loop_required>

<!-- RAG and retrieval controls -->
<rag_permitted>true</rag_permitted>
<rag_indexing_allowed>true</rag_indexing_allowed>
<rag_embedding_scope>summaries_only</rag_embedding_scope>
<rag_chunking_constraints>max_512_tokens</rag_chunking_constraints>
<rag_query_restrictions>support_intent_only</rag_query_restrictions>
<rag_output_attribution_required>true</rag_output_attribution_required>

<rag_output_transformation_required>summarize_and_redact</rag_output_transformation_required>

  <rag_pii_exposure_allowed>false</rag_pii_exposure_allowed>
  <rag_sensitive_data_exposure_allowed>false</rag_sensitive_data_exposure_allowed>
  <rag_downstream_sharing_permitted>false</rag_downstream_sharing_permitted>
  <rag_caching_allowed>true</rag_caching_allowed>
  <rag_cache_retention unit="day">30</rag_cache_retention>
  <rag_audit_required>true</rag_audit_required>
  <rag_audit_retention unit="day">90</rag_audit_retention>
  <rag_model_scope>enterprise_internal_models</rag_model_scope>

<!-- Document training controls -->
<training_permitted>false</training_permitted>
<training_scope>none</training_scope>
<training_purpose>none</training_purpose>
<training_model_type>none</training_model_type>
<training_dataset_reuse_allowed>false</training_dataset_reuse_allowed>

<training_derivative_sharing_permitted>false</training_derivative_sharing_permitted>
  <training_pii_included>false</training_pii_included>
  <training_sensitive_data_included>false</training_sensitive_data_included>
  <training_provenance_required>true</training_provenance_required>
  <training_audit_required>true</training_audit_required>
  <training_audit_retention unit="day">365</training_audit_retention>
  <model_output_usage_constraints>internal_only</model_output_usage_constraints>
  <right_to_be_forgotten_applicability>true</right_to_be_forgotten_applicability>

</head>

```

```
<!-- document content -->  
</doclang>
```

Notes:

- The example uses illustrative values. Implementations SHOULD define controlled vocabularies for enums such as `pii_status`, `pii_sensitivity_level`, `extraction_scope`, `rag_embedding_scope`, and `training_model_type`.
- When `training_permitted` is `false`, implementations SHOULD treat training-related fields as either omitted or set to explicit "none" values.
- Where retention elements include a `unit` attribute, producers MUST use consistent units and pre-normalized values.